

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-141-203420000

LEASE NAME Betty DeMoss

WELL NUMBER 3  
2,970 Ft. from S Section Line

430 Ft. from W Section Line  
SEC. 6 TWP. 9 RGE. 11 (E) or (W)

COUNTY Osborne

Date Well Completed 10-28-98

Plugging Commenced 10-28-98

Plugging Completed 10-28-98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Brungardt Oil & Leasing Co.

ADDRESS PO Box 871, Russell, Kansas 67665

PHONE# (785) 483-4975 OPERATORS LICENSE NO. 3956

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-28-98 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.O. 4,101'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	217'	Cmtd. w/140 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Push bridge plug to 1,000', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 700', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 260', pump 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 55184

Address Shields Bldg., Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brungardt Oil & Leasing Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman Contractor (Employee of Operator) or Operator

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.


(Signature) Jack P. Beeman, Sec - Trust

(Address) Shields Bldg. Russell, Kansas 67665

SUBSCRIBED AND SWORN TO before me this 4th day of January, 19 98

My Commission Expires:

RUTH PHILLIPS  
State of Kansas  
My Appt. Exp. 5-26-99




# Shields

Russell, Kansas

## WELL LOG

Operator: Brungardt Oil & Leasing Co.  
 Well: Betty DeMoss #3  
 Commenced: October 19, 1998  
 Completed: October 28, 1998  
 Contractor: Shields Drilling Co.

Well Description: 100' East of SW SW NW  
 Sec. 6-9S-11W  
 Osborne Co., Kansas



Elevation: 1,869' KB

Treatment:

Production: D & A

Tops:

### CASING RECORD

Size	Run	Pulled
8 5/8"	217'	Cmtd. w/140 sax

..... Figures Indicate Bottom of Formations .....

Rock & shale	150'	
Shale	220'	
Shale & sand	975'	
Anhydrite	1,005'	
Sand & shale	1,366'	
Shale	2,375'	
Shale & lime	3,151'	
Lime	4,101'	RTD

RECEIVED  
 OCT 28 1998  
 OSBORNE COUNTY  
 RECORDS DEPARTMENT

Notes