

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-141-203080000

LEASE NAME Wilcoxson

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

3,630 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 28 TWP. 9 RGE. 12 (X) or (W)

COUNTY Osborne

Date Well Completed 10-16-95

Plugging Commenced 10-16-95

Plugging Completed 10-16-95

LEASE OPERATOR ESP Development, Inc.

ADDRESS 17746 177th Blvd., Paradise, KS. 67658

PHONE#(913) 998-4413 OPERATORS LICENSE NO. 6194

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-16-95 (date)

by Ed Schumacher (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3,130'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	211'	Cmtd. w/140 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Push bridge plug to 830', pump 20 sax cement on plug thru drill pipe. Push bridge plug to 640', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 240', pump 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 10 sax cement down mouse hole  
(if additional description is necessary, use BACK of this form.)  
and 15 sax cement down rat hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5,184

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ESP Development, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of Operator) or Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

REC D  
10-26-95

(Signature) Jack P. Beeman, Sec - Treas

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 25th day of October, 19 95

Ruth Phillips  
Notary Public

My Commission Expires: 5-26-99






# Shields

WELL LOG

15-141-20308-00-00 <sup>Russell, Kansas</sup>

Operator: ESP Development, Inc.  
 Well: Wilcoxson #1  
 Commenced: October 10, 1995  
 Completed: October 16, 1995  
 Contractor: Shields Drilling Co.

Well Description: NE SE NE  
 Sec. 28-9S-12W  
 Osborne Co., KS.



CASING RECORD		
Size	Run	Pulled
8 5/8"	211'	Cmtd. w/140 sax

Elevation: 1,744' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations .....

Shale	214'	
Shale & sand	813'	
Anhydrite	844'	
Shale	1,905'	
Shale & lime	3,010'	
Lime	3,130'	RTD

Notes