

API NUMBER 141-20,3260000

LEASE NAME Kendig

WELL NUMBER 1

330 Ft. from S Section Line

1,320 Ft. from ~~W~~<sup>W</sup>~~XX~~ Section Line

SEC. 29 TWP. 9 RGE. 12 (E) or (W)

COUNTY Osborne

Date Well Completed 9-25-96

Plugging Commenced 9-25-96

Plugging Completed 9-25-96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F.G. Holl Company

ADDRESS P.O. Box 780167, 6427 E. Kellogg #1

PHONE#(913) 346-5868 OPERATORS LICENSE NO. 5056

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-25-96 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3,520'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	215'	Cmtd w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from     feet to     feet each set  
Push bridge plug to 1,080', spot 25 sax cement on plug thru drill pipe. Push plug to 840', pump 100 sax cement on plug thru drill pipe. Push plug to 270', pump 40 sax cement on plug thru drill pipe. Push plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Box 709 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. Holl Company

STATE OF Kansas COUNTY OF Russell, ss.

Jack P. Beeman, Sec-Treas.

(Employee of ~~OPERATOR~~) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 30th day of September, 1996

Ruth Phillips  
Notary Public

My Commission Expires: \_\_\_\_\_






# Shields

Russell, Kansas

## WELL LOG

Operator: F. G. Holl Company  
 Well: Kendig #1  
 Commenced: September 17, 1996  
 Completed: September 25, 1996  
 Contractor: Shields Drilling Co.

Well Description: S/2 S/2 SW/4



Sec. 29-9S-12W  
 Osborne Co., Kansas

Elevation: 1,944' K.B.

Treatment:

Production: D & A

Tops:

### CASING RECORD

Size	Run	Pulled
8 5/8"	215'	Cmtd w/150 sax

..... Figures Indicate Bottom of Formations .....

Post rock & shale	163'
Shale	1,072'
Anhydrite	1,105'
Shale	2,533'
Shale & lime	2,905'
Lime	3,157'
Shale	3,213'
Lime	3,270'
Lime & shale	3,395'
Lime	3,520' RTD

RECEIVED  
 SEP 27 1996  
 OIL & GAS DIVISION  
 KANSAS DEPARTMENT OF REVENUE