


15-141-00039-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Osborne County. Sec. 27 Twp. 9 Rge. 15 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner White Trans Era Petroleum, Inc.  
Lease Name White Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6/10/55 19  
Application for plugging filed 6/9/55 19  
Application for plugging approved 6/9/55 19  
Plugging commenced 6/10/55 19  
Plugging completed 6/10/55 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Milton Galyardt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3872 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	199	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud to 195 feet and laid 1st plug. Used 1/3 sack hulls and 20 sacks cement through drill pipe. Laid 2nd plug. Filled hole to 35' with heavy mud, using 1/3 sack hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Trans Era Petroleum, Inc.  
Address Box 633, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
Robert B. Snyder (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert B. Snyder

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 20th day of June, 19 55

My commission expires 1-30-55

Margie Cooper Notary Public.

**PLUGGING**  
FILE SEC 22 T 9 R 15  
BOOK PAGE 125 LINE 43

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 22 1955  
6-22-1955  
CONSERVATION DIVISION  
Wichita, Kansas

Trans Era Petroleum, Inc.  
White #1

SE SE NW 2719-15  
OSBORNE COUNTY, Kansas

Total Depth: 3872

Comm: 5/28/55  
Comp: 6/10/55

Casing  
8 5/8" @ 199\*

Cement  
140 Sacks Lone Star

FORMATION	DEPTH
Shale & Shells	475
Shale & Sand	950
Red Bed & Shale	1100
Red Bed	1240
Anhydrite	1280
Shale, Sand & Shale	1310
Shale	1660
Shale & Lime	3240
Lime	3523
Lime & Shale	3630
Lime, Shale & Chert	3695
Cherty Cong.	3723
Conglomerate	3772
Shale & Lime	3797
Shale & Lime	3845
Arbuckle Lime	3872

STATE OF KANSAS )  
COUNTY OF RUSSELL ) SS:

I hereby certify that the above information is true and correct to the best of my knowledge.

*Robert B. Snyder*

Subscribed and sworn to before me this 20th day of June, 1955.

*Margie Cooper*  
Notary Public

My commission expires: 1-30-57.

**PLUGGING**  
FILE SEC 22 9 R 15W  
BOOK PAGE 125 Line 43

6-22-1955