

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-63605-00-01
API NUMBER N/A Compl't date 5-29-47
LEASE NAMED Dorr

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 502
1650 Ft. from S Section Line
4950 Ft. from E Section Line

LEASE OPERATOR Gold Petroleum Inc.
ADDRESS 3917 South Peachway Denver, Colo. 80237-0242
PHONE# (303) 758-3591 OPERATORS LICENSE NO. 31233

SEC. 16 TWP. 9 RGE. 16 ~~N50XX~~ (W)
COUNTY Rooks
Date Well Completed 5-29-47
Plugging Commenced 2-22-94
Plugging Completed 2-22-94

Character of Well injection
(Oil, Gas, D&A, SWD, Input, Water Supply Well)
The plugging proposal was approved on 2-21-94 (date)

by Dennis Hamel (KCC District Agent's Name).
Is ACO-1 filed? No If not, is well log attached? Not Available

Producing Formation LKC Depth to Top 3120 Bottom 3334 T.D. 3336
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|------|----------|--------|------------|
| LKC | 3120-28 | 0 | 239 | 8 5/8ths | 239 | none |
| 3326-34 | 3152-63 | 0 | 3351 | 4 1/2 | 3351 | none |
| 3306-17 | 3170-74 | | | | | |
| | 3190-98 | | | | | |
| | 3288-95 | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
2 3/8ths tubing run to 3064 pumped 200lbs of hulls and 50sks of cement pulled tubing back to 2000 ft mixed 200lbs of hulls with 75 sks of cement pulled tubing out of hole mixed 25 sks of cement Max pressure 600lbs shut in at 400lbs. between 85/8ths and 4 1/2 100 lbs hulls and 50sks of cement, 300# shut in at 100# (If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Allie cementing Inc License No. N/A
Address P.O. BOX 31 Russell Ks 67665

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1994 3/11/94

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gold Petroleum Inc
STATE OF Denver Colo. COUNTY OF

Carl Zimmerman (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carl Zimmerman
(Address) P.O. Box 53 Schoenchen Ks 67667



SUBSCRIBED AND SWORN TO before me this 10th day of March, 1994

Roxann Zimmerman
Notary Public

My Commission Expires: 4/3/97