


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks

County. Sec. 18 Twp. 9S Rge. 16W (X) (W)

Location as "NE/CNW/SW" or footage from lines C E/2 NE NW

Lease Owner V. E. Sheffer KCC 240

Lease Name James Colahan Sr. Estate Well No. 1

Office Address Box 653 Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil-depleted

Date well completed February 14, 19 49

Application for plugging filed July 5, 19 60

Application for plugging approved July 5, 19 60

Plugging commenced October 12, 19 60

Plugging completed October 12, 19 60

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3438 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	213'	None
				5 1/2"	3350'	1700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

10 3/4" 213' circulated with cement.  
5 1/2" 3350' with 125 sacks cement.  
Filled with sand to 3300', set 4 sacks cement with dump bailer, pulled 1700', 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550' (70 sacks Gel), displaced 20 sacks cement through 5 1/2" at 550', heavy mud to 190', displaced 20 sacks cement through 5 1/2" at 190', heavy mud to 30', set plug and 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C. E. Shull


Address Great Bend, Kansas # 8

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *V. E. Sheffer*

(Address)



Subscribed and sworn to before me this 8th day of August, 1968  
*Jo Ann Sechten*  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 9 1968  
CONSERVATION DIVISION  
Wichita, Kansas

8/9/68

Commenced: Jan. 26, 1949  
Completed: Feb. 14, 1949

Re

WELL LOG

15-163-03618-00-00

ALKAY OIL COMPANY  
NO. 1-~~COLEMAN~~ Colahan <sup>KCC</sup> <sub>ZAP</sub>  
C E  $\frac{1}{2}$  NE NW 18-9S-16W  
Rooks County, Kansas

CASING RECORD:  
213' 10 3/4" 200 Sax Cement  
3350' 5 1/8" 125 Sax "

Elevation - 2007 Kelly Bushing  
2005 Derrick Floor  
1999 Ground  
All measurements  
from Derrick Floor

Pot. 30 barrels

FROM	TO	
0	40	Surface Clay
40	190	Shale & Sand
190	645	Shale & Sand
645	1245	Shale & Shells
1245	1285	Anhydrite
1285	1805	Shale & Shells
1805	1975	Shale & Lime
1975	1980	Lime & Shale Streaks
1980	2265	Lime
2265	2350	Lime & Shale Streaks
2350	2530	Broken Lime
2530	2600	Shale & Lime
2600	2780	Shale & Shells
2780	2885	Shale & Lime
2885	3023	Broken Lime
3023	3036	Lime & Shale
3026	3130	Broken Lime
3130	3438	Lime
	3438	T. D.

TOPS:

Kanas City 3124 -1119 ✓

Note: PLUGGING REQUEST MAILED JULY 2nd., 1960. V.E. Sheffer