

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-163-0146(-01-01)

LEASE NAME Overholser

WELL NUMBER 3

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 20 TWP. 9S RGE. 16 ~~W~~ or (W)

COUNTY Rooks

Date Well Completed 12-15-62

Plugging Commenced 7-22-87

Plugging Completed 7-22-87

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Harold Krueger Co.

ADDRESS Box 247, Natoma, Kansas 67651

PHONE# (913) 885-4701 OPERATORS LICENSE NO. 5769

Character of Well Inj.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks. Dennis Hamel

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation NA Depth to Top \_\_\_\_\_ Bottom T.D. 3460'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	198	None
				5 1/2	3460	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Mixed 50 sks. cement, followed with 50 sks. cement w/hulls down tubing. Cement circulated to top. Pulled tubing out and hooked onto casing and mixed 200 sks. cement w/hulls at 500 psi. Shut in @100 psi. Mixed 50 sks. cement and put down annulus. Shut in @100 psi. Well plugged. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. \_\_\_\_\_

Address Russell, Kansas

STATE OF KANSAS COUNTY OF OSBORNE, ss.

Dean E. Wineland (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dean E. Wineland

(Address) Natoma, Kansas 67651

SUBSCRIBED AND SWORN TO before me this 18<sup>th</sup> day of August, 19 87

Larry Doty  
 Notary Public  
 STATE CORPORATION COMMISSION

My Commission Expires: 12-15-88

AUG 19 1987 8/19/87

Form CP-4  
 Revised 08-84

CONSERVATION DIVISION  
 Wichita, Kansas