


15-163-01011-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

ROOKS County. Sec. 1 Twp. 9 Rge. 17W (E) (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW NE NE
Lease Owner Rosencrantz-Bemis Drilling Company
Lease Name Hrabe Well No. 1
Office Address P. O. Box 713, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-21 19 63
Application for plugging filed 5-21 19 63
Application for plugging approved 5-21 19 63
Plugging commenced 5-21 19 63
Plugging completed 5-21 19 63
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3395 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Soil Post						
Rock and Blue Shale	Casing	0'	216'	8 5/8"	216'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED: Filled Hole with heavy mud from
3395' up to 550' with 1/4 sk hulls,
20 sacks cement through drill pipe.
Filled hole with mud to 200', 1/4 sk
hulls, 20 sk cement through drill pipe.
Filled hole with mud up to 35', 1/4 sk
hulls, 10 sacks cement to cellar Zero.

6/5/63
RECEIVED
STATE CORPORATION COMMISSION

JUN 5 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rosencrantz-Bemis Drilling Company
Address P. O. Box 713, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
O. E. Rosencrantz-President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. E. Rosencrantz
P. O. Box 713, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1 day of June 19 63

My commission expires January 2, 1966 Thomas W. Hummer Notary Public.

15-163-1011-0-00

WELL LOG

ROSENCRANTZ-BEMIS DRILLING COMPANY-OPERATOR

ROSENCRANTZ-BEMIS DRILLING COMPANY-CONTRACTOR

HRABE #1
SW NE NE
Sec 1-9-17W
Rooks County, Kansas

T.D.: 3395'

COMMENCED: 5-11-63
COMPLETED: 5-21-63

CASING:
8 5/8" Set @ 216'

CEMENT:
with 112 sk Pozmix

FORMATION	DEPTH
Post Rock	40
Blue Shale	217
Shale	760
Sand Shale	940
Red Bed Shale	1220
Anhydrite	1275
Shale and Shells	1675
Lime and Shale	2830
Lime	2865
Lime and Shale	3049
Lime	3395

6/5/63
RECEIVED
STATE CORPORATION COMMISSION

JUN 5 1963

CONSERVATION DIVISION
WICHITA, KANSAS