

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-143-01470-00-01  
Compl 6/63

LEASE NAME Hrabe "A"

WELL NUMBER 5

2310 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 1 TWP. 9S RGE. 17W (E) or (W)

COUNTY Rooks

Date Well Completed 6/63

Plugging Commenced 3/21/89

Plugging Completed 3/28/89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

PHONE#( ) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Feb. 28, 1989 (date)

by District #4 (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation Cedar Hills Depth to Top 934' Bottom 970' T.D. 1054' (PBTD)

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Put out
				8 5/8"	158'	-
				5 1/2"	3519'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

3/21 Plugged dwn 5 1/2" csg w/135 sx 65/35 Pozmix w/8% gel, 1/4# flocele, 3 sx hulls. MP 300 psig, STP 200 psig. Plugged down 8 5/8" csg w/15 sx. 65/35 Pozmix w/8% gel, 1/4# flocele. MP 500 psig. JC 4:30 pm. 3/22 Tag cmt 330'. 3/28 Filled 5 1/2" csg to surface w/1 3/4 yds Redi-Mix.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033

Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company

STATE OF KS COUNTY OF Sedgwick, ss.

Larry M. Jack, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) By: Larry M. Jack

(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 5 day of April, 1989



Kerran Redington Notary Public