


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

R 15-163-03628-00-00
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rooks County. Sec. I6 Twp. 9S Rge. T6W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SW/ SW/ NW/
Lease Owner Morgenstern & Specter
Lease Name ~~Finnesey~~ ^{KCC} ~~Finnesey~~ ^{HW} Well No. I
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 8-21-57 19____
Application for plugging filed April 28, 1960 19____
Application for plugging approved April 29, 1960 19____
Plugging commenced 5/3/60 19____
Plugging completed 5/24/60 19____
Reason for abandonment of well or producing formation _____
Failure to produce profitably
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation K.C. Depth to top 3139 Bottom 3389 Total Depth of Well 3390 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	206	none
				5 1/2		250 1/2 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 3320 feet, Dumped 5 Sacks Cement.
Circulated Mud at 550 feet, And Pumped 15 Sacks Cement
at 170 feet, Set a Rock Bridge at 25 feet,
Then filled up with Cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1960
6/6/60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor E. & L. CASING PULLING COMPANY NO. 377
Address GREAT BEND, KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.
Morgenstern & Specter, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Morgenstern & Specter
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of June, 19 60

My commission expires April 1963

Elsie Crady
Notary Public.



15-163-03628-00-00

Sierra Petroleum Co., Inc.

Finney ^{KCC} _{ZHP}
~~FINNEY~~ #1

Sec

SW NW Sec. 16-9S-16W
Rooks County, Kansas

Total Depth: 3390'

Comm: 7/24/57

Comp: 8/1/57

Casings:

8 5/8 @ 206

5 1/2 @ 3339

Cement:

with 125 sacks cement

with 100 sacks cement

FORMATION	DEPTH
Clay	30
Shale	200
Shells	206
Shale & shells	665
Shale & sand	700
Shale, shells & sand	805
Shale & sand	950
Red bed	1252
Anhydrite	1287
Shale & shells	1730
Lime & shale	2140
Lime	2370
Lime & shale	3000
Lime	3337
K. C.	3390
Tops: Heebner	3098
Toronto	3120
L. K. C.	3139

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. D. Hawkins

Subscribed and sworn to before me this 5th day of August, 1957.

Margie Cooper
Notary Public

My commission expires: 1-30-61.