

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-03750-01

LEASE NAME Tatkenhorst Home

WELL NUMBER 2

990 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 11 TWP. 9 RGE. 16 (E) (W)

COUNTY Rooks

Date Well Completed 5-27-49

Plugging Commenced 12-18-87

Plugging Completed 12-18-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Harold Krueger Co.

ADDRESS Box 247, Natoma, Kansas 67651

PHONE# (913) 885-4701 OPERATORS LICENSE NO. 5769

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-18-87 (date)

by Dennis L. Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

RECEIVED
 STATE CORPORATION COMMISSION
 1/13/88

Producing Formation KC Lime Depth to Top 3080 Bottom 3290 T.D. 3292

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				7	3292	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped in 7" csg.: 50 sx. cement w/ $\frac{1}{2}$ " flocele, plus 250 sx w/ 8 sx. hulls.

Max. 900# P.S.I. Perf. csg. at 110'. Pumped 100 sx. cement. Circ. cement to surface.

El. 2070. Top Fluid at 1500' before perf. Well plugged. Job complete.

Also perf. casing 3 holes @1250' and 3 holes @700'.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No.

Address Hays, Kansas 67601

STATE OF KANSAS COUNTY OF OSBORNE, ss.

Dean E. Wineland

(Employee of Operator) or ~~(Operator)~~

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dean Wineland

(Address) Natoma, Kansas 67651

SUBSCRIBED AND SWORN TO before me this 12th day of January, 19 88

Lois A. Doty
 Notary Public

My Commission Expires: 12-15-88

