

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-163-03732-00-00
 API NUMBER 15-163-2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Tatkenhorst C

WELL NUMBER 4

1650 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR Harold Krueger Co.

SEC. 11 TWP. 9 RGE. 16 (XXX(W))

ADDRESS Box 247, Natoma, Kansas 67651

COUNTY Rooks

PHONE# (913) 885-4701 OPERATORS LICENSE NO. 5769

Date Well Completed 10-30-40

Character of Well _____

Plugging Commenced 9-25-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well!)

Plugging Completed 9-25-87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas Dennis Hamel

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation KC Lime Depth to Top 3050 Bottom 3172 T.D. 3199

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				5 1/2	3172	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spot first plug @3178. 70 sks econolite; 1/2# flocele and 4 sks hulls. Displace with 5 bbls water. Pull tubing to 1228. Perforate @1325. Spot 12 bbl cement, 1/2 sk. flocele; 1/2 sk hulls and 20 sks. econolite. Pull tubing. Perforate @750. Spot 12 bbl cement; 1/2 sk hulls, 20 sks. econolite, 1/2# flocele. Pull tubing. Perforate @200. Tie on to casing. Start cement; 1/2 sk hulls. Cement circulated to surface. Close in well @ well head. Job completed.

Name of Plugging Contractor Halliburton License No. _____

Address Hays, Kansas 67601

STATE OF KANSAS COUNTY OF OSBORNE, ss.

Dean E. Wineland (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dean E. Wineland

(Address) Natoma, Kansas 67651

SUBSCRIBED AND SWORN TO before me this 16th day of October, 19 87



Lois A. Doty
 Notary Public

My Commission Expires: 12-15-88

10/19/87
 1987