

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

#4 API NUMBER 15-163-01463-00-00
N/A

LEASE NAME Casey

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

4290 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 21 TWP. 9S RGE. 16 ~~W~~ or (W)

COUNTY Rooks

Date Well Completed 4-27-54

Plugging Commenced 3-24-88

Plugging Completed 3-24-88

LEASE OPERATOR H & C Oil Operating, Inc.

ADDRESS P.O. Box 86 Plainville, Ks. 67663

PHONE# (913) 434-7434 OPERATORS LICENSE NO. 8914

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Kansas City Depth to Top 3208 Bottom 3409 T.D. 3425

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Lime	0	158	8 5/8	158'	0
		0	3418	5 1/2"	3418'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Mixed and pumped 50 sacks down annulus. Shut in pressure 300#. Mixed and pumped 300 sacks with 500# Hulls down 5 1/2" casing. Shut in pressure 200#. Used 500# Hulls and 350 sacks Thrifty-mix cement

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BJ Titan Services License No. _____

Address Hays, Ks. 67601

STATE OF Kansas COUNTY OF Rooks, ss.

Charles R. Ramsay (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Charles R. Ramsay

(Address) P.O. Box 86 Plainville, Ks. 67663

SUBSCRIBED AND SWORN TO before me this 6th day of April, 19 88

Arene Zellholter
Notary Public

My Commission Expires: APR - 7 1990





Filed for Harry Gore-Veeder Supply & Dev. Co. Farm Casey No. 2 Depth 3425'
 Contractor Veeder Supply & Development Co. Pipe 158' 8 5/8" csg. cemented w/80 sacks cement.
 Location SE NW NE Sec. 21 Twp. 9 Range 16
 Commenced 4-17-54 Completed 4-27-54 County Rooks State Kansas

Potential: 104 Bbls. Elevation: 2075 KB

Surface soil	0	10	10	TOPS:	
Shale	10	80	70	Topeka	2938
Sand, shale	80	120	40	Heebner	3165
Shale	120	390	270	Toronto	3185
Shale, shells	390	580	190	Lansing KC	3208
Shale, sand red sand	580	980	400		
Shale, shells	980	1150	170		
Shale, red bed	1150	1308	158		
Anhydrite	1308	1347	39		
Shale, shells	1347	2140	793		
Shale, lime	2140	2964	824		
Broken lime, shale	2964	2980	16		
Lime, shale	2980	3272	282		
Lime	3272	3425	153		
Total Depth	3425				

AFFIDAVIT

STATE OF KANSAS) SS
 Montgomery County)

Floyd W. Hild, of lawful age, being duly and solemnly sworn on oath, deposes and says:

That I am a resident of Cherryvale, Kansas; and I hereby know and on oath state that the above drilling log covering the Casey #2 Well located in Section 21-9-16, Rooks County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

BY Floyd W. Hild
 Floyd W. Hild

Subscribed and sworn to before me this 29th day of April, 1954.

Colles Dawson
 Notary Public

My commission expires July 11, 1956.

STATE CORPORATIONS DIVISION
 APR - 30 1954
 CHERRYVALE, KANSAS
 3/3/88