

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200, Colorado Derby Building  
Topeka, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

WELL WAS COMPLETED ON  
API NUMBER 7-11-56

15-163-03641-00-01

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

DPW  
KCC  
990'

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE#(405) 749-2471 OPERATORS LICENSE NO. 5447

Character of Well Input

(Oil, Gas, DRA, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 8, 1990 (date)

by Mr. Gib Sheck (KCC District Agent's Name).

Well was completed on:  
Is ACO-1 filled? 7-11-56 If not, is well log attached? Yes

Producing Formation Toronto LKC Depth to Top 3184 Bottom 3400 T.D. 3470'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Toronto	(Ini. well)	3184	3400	9 5/8"	246'	
LKC	(Ini. well)			5 1/2"	3470'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Tied onto the 8 5/8" surface csg and pumped down annulus 60 sx 65/35 poz. w/6% gel + 100 # hulls. Tied onto the 5 1/2" csg and filled to surface W/50 sx smt + 150 # hulls, followed by 240 sx 65/35 Poz w/6% gel and 550 # hulls. State Witness: Mr. Gib Sheck.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Service Co. License No.

Address Oberlin, Kansas 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma ,ss.

Bryan Humphries (Employee of Operator) or (Operator) of  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,  
statements, and matters herein contained and the log of the above-described well as filed that  
the same are true and correct, so help me God.

(Signature) *Bryan Humphries*

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 29th day of May , 1990

My Commission Expires: 4-16-94

*Kay Ann Kilmer*  
Notary Public

15-163-03641-00-01

EXPLORATION RECORD

1 - Bw<sup>1</sup> . Prod.  
 1 - Di<sup>1</sup> .  
 1 - District  
 1 - Geological Dept. - Bville.  
 1 - Geological Dept. - District

Lease Casey

DORR UNIT #903W

Well

3

Formation Name	Top	Base	Remarks
Clay and shale	0	225	
Sand	225	352	
Sand and shale	352	410	
Shale	410	656	
Lime and shale	656	1858	
Lime	1858	2049	
Lime and shale	2049	2388	
Lime	2388	2444	
Lime and shale	2444	2938	
Lime	2938	3324	
Lime and chert	3324	3381	
Lime	3381	3470	

FORMATION TOPS - Sample

Anhydrite	Not picked (1285 Howes Log)	TOP DAKOTA 514' BASE " 995'
Base Anhydrite	Not Picked (1322 Howes Log)	
Howard	2938	
Topaka	2964	
Heebner	3164	
Toronto	3185	
Lansing-Kansas City	3206	
Drum	3343	
Base-Kansas City	3458	
Rotary Total Depth	3470	
Cable Tool TD	3363	

RECEIVED  
STATE CORPORATION COMMISSION

MURKIN/VALLEY DIVISION  
Wichita, Kansas