

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-163-00876-00-00
WELL PLUGGING RECORD

NORTH

Locate well correctly on above Section Plat

Rooks County. Sec. 22 Twp. 9 Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines NE 34 NW
Lease Owner Rupp-Ferguson Oil Co.
Lease Name Casey Well No. 1
Office Address 523 Petroleum Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-5-55 19
Application for plugging filed 12-5-55 19
Application for plugging approved 12-5-55 19
Plugging commenced 12-5-55 19
Plugging completed 12-5-55 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3669 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	196	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole w/mud to 192', 1/2 sack hulls, plug, 20 sacks cem.
Fill w/mud to 40', 1/3 sack hulls, plug, cem. to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.
Address 523 Petroleum Bldg., Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. W. Knox (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. D. Enos
523 Petroleum Bldg., Wichita, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 55

My commission expires 3-4-56
Helen Horine Notary Public.

PLUGGING
FILE REC 22 T 9 R 16W
BOOK PAGE 22 LINE 3

12-10-55

15-163-00876-00-00

CONTRACTOR'S WELL LOG

Rupp-Ferguson No. 1 Casey
NE SE NW, Sec. 22-9-16W,
Rooks County, Kansas
Commenced: 11-26-55
Completed: 12-5-55
Set 196' of 8 5/8" surface casing w/150 sacks cement

Elev. 2079 KB

D & A

193 rock & shale
580 shale
990 sand
1305 red bed
1340 Anhydrite
1800 shale & shells
1965 shale & lime streaks
3008 lime & shale
3070 lime
3140 lime & shale
3507 lime
3577 lime & shale
3629 Cong.
3669 Arb. F.D.

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I, L. W. Knox, Landman for Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Casey well.

L. W. Knox
L. W. Knox

Subscribed and sworn to before me this 8th day of December, 1955.

Helen Horine
Notary Public

My Commission Expires June 4, 1959.

PLUGGING
FILE SEC 22 9 R 16W
BOOK PAGE 22 LINE 3

RECORDED
INDEXED
CONTRACTOR'S DIVISION
Wichita, Kansas

12-10-55