


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-163-00839-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rooks County. Sec. 23 Twp. 9 Rge. 16 (E) (W)
Location as "NE/CNW%SW%" or footage from lines SE SE SE
Lease Owner Petroleum, Inc.
Lease Name SARVER 'A' Well No. 1
Office Address 311 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 12 1955
Application for plugging filed August 12 1955
Application for plugging approved August 12 1955
Plugging commenced August 12 1955
Plugging completed August 12 1955
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3712 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	325'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up to 230' and set first plug at 230',
placed 1/2 sack hulls on top of plug followed by 15
sacks cement. Mudded up to 40' and set second plug
with 1/2 sack hulls on top of plug followed by
10 sacks cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Karl E. Becker (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl E. Becker

311 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of August, 1955

My commission expires August 8, 1959

Gloria Morrison
Notary Public.

PLUGGING
FILE SEC 23 T 9 R 16 W
BOOK PAGE 142 LINE 32


RECEIVED
STATE CORPORATION COMMISSION
8-25-55
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

15-103-00839-00-00

COMPANY **Petroleum, Inc.**
 FARM **SARVER 'A'** NO. **1**
 TOTAL DEPTH **3712'**
 COMM. **August 1, 1955** COMP. **August 12, 1955**
 CONTRACTOR **Garvey Drilling Company**
 CASING **8-5/8" @ 239' w/140 ann**

SEC. **23** T. **9S** R. **16W**
 LOC. **86 82 82**
885' FSL
130' FSL
 COUNTY **Rock County**



ELEVATION **2076' TP**
2078' SB
 PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

90	Rock & Clay
170	Rock, Sand and Shale
200	Rock & Sand
239	Thin Shale
295	Shale
350	Sand
1280	Sand, Shale & Shells
1310	Argillite
1830	Shale & Shells
2765	Shale & Lime
2925	Lime
3111	Lime & Shale
3197	Lime
3255	Lime & Shale
3543	Lime
3600	Lime & Shale
3631	Conglomerate
3662	Lime & Chert
3682	Artnuckle
3692	Chert & Shale
3712	Artnuckle

R.T.D. 3712'

Geological Tops

Topokan	2917	(- 909)
Hickory	3216	(-1218)
Toronto	3211	(-1213)
Lansing	3250	(-1252)
Base Kansas City	3193	(-1215)
Artnuckle	3692	(-1614)

PLUGGING

FILE SEC 23 T 9 R 16W

BOOK PAGE 142 LINE 32

State of KANSAS
 County of SENECA } SS:
 I, Karl E. Becker

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 1 1955
 CONSERVATION
 Michigan
 Petroleum, Inc.

8-25-55

upon oath state that the above and foregoing is a true and correct copy of the log of the SARVER 'A' #2 well

Subscribed and sworn to before me this 18th day of August 1955

Karl E. Becker

My Commission Expires: July 8, 1958

D. M. Kennedy
 NOTARY PUBLIC