

15-163-22216-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-163-22,216
LEASE NAME Rathburn
WELL NUMBER 1
SPOT LOCATION C S/2 NE NE
SEC. 23 TWP. 9S RGE. 16 (E) DR (W)
COUNTY Rooks
DATE WELL COMPLETED 11-27-83
PLUGGING COMMENCED 11-27-83
PLUGGING COMPLETED 11-27-83

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR DaMar Resources, Inc.
ADDRESS P. O. Box 70, Hays, Kansas 67601
PHONE #(913) 625-0020 OPERATORS LICENSE NO. 9067

CHARACTER OF WELL D&A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes
WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? District #6
IS ACO-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 3630'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	274'	-0-

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Mud laden fluid @ 3630' - 1320'
20 sks cement @ 1320'
100 sks cement @ 870'
40 sks cement @ 275'
10 sks cement @ 40'
10 sks cement in rathole.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)


NAME OF PLUGGING CONTRACTOR Emphasis Oil Operations LICENSE No. 750
ADDRESS P. O. Box 506, Russell, Kansas 67665-0506

STATE OF KANSAS COUNTY OF RUSSELL, SS.

Joe K. Branum (EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT, SO HELP ME GOD.

(SIGNATURE) Joe K. Branum
(ADDRESS) P. O. Box 506, Russell, KS 67665

SUBSCRIBED AND SWORN TO BEFORE ME THIS 2nd DAY OF December, 1983



Glenda R. Tiffin
Glenda R. Tiffin, NOTARY PUBLIC

MY COMMISSION EXPIRES: February 6, 1984.

Rec'd
12-5-83

19-163-22216-00-00

EMPHASIS OIL OPERATIONS

P. O. Box 506

Russell, Kansas 67665-0506

DRILLERS LOG

OPERATOR: DaMar Resources, Inc.
P. O. Box 70
Hays, Kansas 67601

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, Kansas 67665-0506

LEASE: Rathburn WELL: #1

LOCATION: C S/2 NE NE
Section 23-9S-16W
Rooks County, Kansas

Total Depth: 3630'

Elevation:

Log Depth: 3622'

Date Completed: 11-27-83

Commenced: 11-19-83

Status: Dry Hole

Casing: 8-5/8" @ 274' with 180 sks cement

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	40'	Sand & Shale	2160'
Sand	200'	Shale	2920'
Shale	276'	Shale & Lime	3429'
Sand & Shale	1302'	Lime	3511'
Anhydrite	1340'	Lime & Chert (R.T.D.)	3630'
Redbed & Sand	1515'		

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)


Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Joe K. Branum

Joe K. Branum

Subscribed and sworn to before me this 2nd day of December, 1983.

My Commission Expires: February 6, 1984.



RECEIVED
STATE CORPORATION COMMISSION
DEC 5 1983
CONSERVATION DIVISION
Wichita, Kansas

Glenda R. Tiffin

Notary Public

12-5-83