

15-163-02935-00 00

WELL PLUGGING RECORD


STATE OF KANSAS  
STATE CORPORATION COMMISSION

OR  
FORMATION PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Strike out upper line  
when reporting plugging  
off formations.

Rooks County. Sec. 25 Twp. 9 Rge. (E) 16 (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines 330 N 330 E of S.W. Corner  
Lease Owner Cities Service Oil Company  
Lease Name Beisner Well No. 1  
Office Address Bartlesville, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6-24 19 47  
Application for plugging filed 6-25 19 47  
Application for plugging approved 6-25 19 47  
Plugging commenced 6-25 19 47  
Plugging completed 6-25 19 47  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. G. E. Stough  
Producing formation Arbuckle Depth to top 3593 Bottom Total Depth of Well 3609 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle Lime	Dry			8 5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud from total depth 3609 to 215' set  
plug dumped 15 sacks cement mud to 43' set plug dumped 10 sacks  
cement mud and dirt to surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to  
Address Box 751, Great Bend Kansas



STATE OF Kansas COUNTY OF Barton, ss.  
R. J. Turner (employee of owner) or Owner or Operator

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. J. Turner

Box 553 Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 1947  
W. G. Smith

My commission expires March 17, 1951

Notary Public.

**PLUGGING**  
FILE SEC 25 T 9 R 16 W  
BOOK PAGE 117 LINE 3

15-163-02935-00-00

Geol., 63 500 5-47

WELL RECORD

Company Citizen Services Oil Co. Well No. 1 Farm Interior  
 Location 320' North and 330' East of SW Corner Sec. 25 T 9 R. 14W  
 Elevation 3050 (3047 G.) County Woods State Kansas  
 Drlg. Comm. June 8, 1947 Contractor H. V. King Drilling Co.  
 Drlg. Comp. June 22, 1947 Acid None  
 T. D. 3609' Initial Prod. None. Dry hole. P & S

LOG RECORD:

7-7/8" x 300' with 125 sacks cement and 1 sack G.C.

FORMATION RECORD:

surface soil & clay	0-20
lime	90
shale	400
red bed & sandy shale	815
shale & shells	1200
shale	1255
anhydrite	1275
shale & shells	1950
lime & shale	2125
lime	2225
lime & shale	2410
lime	2490
shale	2540
shale & lime	2660
shale	2790
lime	2825
lime & shale	3175
lime	3241
lime & shale	3531
conglomerate	3595
conglomerate & lime	3609 TD

Schlumberger

Top Lassing	3027'
Top Conglomerate	3551'
Top Anhydrite	3595'
Penetration	26'
Total Depth	3609'

LOG:

300'	-	OK
1000'	-	OK
1500'	-	OK
2000'	-	OK
2500'	-	OK
3000'	-	OK

7-7/8" rotary hole.

7-17-47

**PLUGGING**  
 FILE SEC 25 T 9 R 16W  
 BOOK PAGE 117 LINE 3