

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
67202 TYPE OR PRINT

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-21479 - 00-00
LEASE NAME HRABE A Wichita, KS

WELL NUMBER 7

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days
330 Ft. from S Section Line
4115 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 1 TWP. 9S RGE. 17W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY ROOKS
PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 12/8/81

Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 7/24/03
Plugging Completed 7/24/03

The plugging proposal was approved on 7/24/03 (date)
by Rich Williams w/KCC Hays, KS. (KCC District Agent's Name).

Is ACO-1 filed? ? If not, is well log attached? no
Producing Formation LKC Depth to Top 3167 Bottom 3433 TD 3490 Show
depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	199	8 5/8	199	0
		production	3489	4 1/2	3489	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Tied onto 4 1/2" csg. Pumped 185 sxs 60-40 poz. 10% gel. 400# hulls. max press 700#. ISIP 600#. Tied onto 8 5/8". Pumped 15 sxs 60-40 poz 10% gel 100# hulls. 500# max press. 500# ISIP. Well P/A. Witnessed and approved by Rich Williams w/ KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300; Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Tom W. Nichols
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 28th day of July, 2003

Notary Public - Barbara J. Dodson Barbara J. Dodson
My Commission Expires: 12/16/03 Form CP-4 Revised 05-88




8/5/03 RECEIVED
AUG 05 2003
KCC WICHITA

ALLIED CEMENTING CO., INC.

P.O. BOX-31
 RUSSELL, KS 67665
 PH (785) 483-3887
 FAX (785) 483-5566
 FEDERAL TAX ID# [REDACTED]

15-163-21479-02-00

 * INVOICE *



Invoice Number: 090479

Invoice Date: 07/29/03 RECEIVED

8/5/03 AUG 05 2003
 KCC WICHITA

Sold Murfin Drilling Co.
 To: 250 N. Water, St. #300
 Wichita, KS
 67202

USED FOR 36-PA
 APPROVED [Signature]

Cust I.D.....: Murfin
 P.O. Number...: Hrabe A-7
 P.O. Date....: 07/29/03
 Due Date.: 08/28/03
 Terms....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	120.00	SKS	7.1500	858.00	T
Pozmix	80.00	SKS	3.8000	304.00	T
Gel	14.00	SKS	10.0000	140.00	T
Hulls	5.00	SKS	18.0000	90.00	T
Handling	250.00	SKS	1.1500	287.50	T
Mileage (43)	43.00	MILE	12.5000	537.50	T
250 sks @\$.05 per sk per mi					
Plug	1.00	JOB	475.0000	475.00	T
Mileage pmp. trk	43.00	MILE	3.5000	150.50	T

All Prices Are Net, Payable 30 Days Following Subtotal: 2842.50
 Date of Invoice. 1 1/2% Charged Thereafter. Tax: 150.65
 If Account CURRENT take Discount of \$ 284.25 Payments: 0.00
 ONLY if paid within 30 days from Invoice Date Total... 2993.15

ALLIED CEMENTING CO., INC. 14955

Federal Tax I.D.# XXXXXXXXXX

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT

15-163-021479-00-00 Russell

DATE <u>7-24/03</u>	SEC.	TWP.	RANGE	CALLED OUT <u>8:00 AM</u>	ON LOCATION <u>9:00 AM</u>	JOB START	JOB FINISH <u>10:00 AM</u>
LEASE <u>Habe</u>		WELL # <u>A-7</u>		LOCATION <u>Paville SE 1E dntd 4N</u>		COUNTY <u>Rock</u>	STATE <u>K</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR C/Plou

TYPE OF JOB _____

HOLE SIZE _____ T.D. _____

CASING SIZE 4 1/2 DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED _____

2500 lbs 60/40-19

500 # 4 1/2 Used 200 lbs

COMMON	<u>320</u>	@	<u>7.45</u>	<u>258.00</u>
POZMIX	<u>80</u>	@	<u>3.80</u>	<u>304.00</u>
GEL	<u>14</u>	@	<u>10.00</u>	<u>140.00</u>
CHLORIDE		@		
<u>Hulls</u>	<u>5</u>	@	<u>18.00</u>	<u>90.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>250</u>	@	<u>1.15</u>	<u>287.50</u>
MILEAGE	<u>54 SK</u>	@	<u>1 Mile</u>	<u>537.50</u>
				TOTAL <u>2217.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Bill

366 HELPER Rael

BULK TRUCK

362 DRIVER Refus

BULK TRUCK

_____ DRIVER _____

REMARKS:

pump down 4 1/2 w 18 1/2 at Cont
w 400 # Hulls max 700 # Shot in 60 #

pump down Backside w 15 1/2
160 # Hulls 500 # Shot in

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 475.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 43 @ 3.50 150.50

PLUG _____ @ _____

_____ @ _____

_____ @ _____

TOTAL 625.50

CHARGE TO: MURFIN

STREET Box 130

CITY Hill City STATE KANSAS ZIP 67642

FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE John Gester

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

RECEIVED
AUG 05 2003
KCC WICHITA

PRINTED NAME
8/5/03