


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rooks County, Sec. 3 Twp. 9S Rge. (E) 17W (W)
Location as "NE/CNW/SW" or footage from lines C N/2 S/2 SW NW
Lease Owner Pickrell Drilling Company
Lease Name Hrabe "B" Well No. 2
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7/23 1967
Application for plugging filed 7/23 1967
Application for plugging approved 7/23 1967
Plugging commenced 7/23 1967
Plugging completed 7/23 1967
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Box 582, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3515 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	217'	None


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 800'. Set plug. Cemented with 90 sacks of cement.
Heavy mud to 210': Set plug. Cemented with 20 sacks cement.
Heavy mud to 40'. Set plug. Cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1967
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts ~~owner or operator~~ (owner or operator) of the above-described



sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Ks.
(Address)

Sworn to before me this 3rd day of August, 19 67

My commission expires May 10, 1970

L. M. Whiting
Notary Public.

15-163-20037-00-00
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas 67202

Rotary Drilling Commenced 7/15/67
Rotary Drilling Completed 7/23/67

LOCATION: Hrabe "B" No. 2
C N/2 S/2 ~~SW~~ Section 3-9S-17W
Rooks County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (11 jts.) 8 5/8" surface pipe set at 217' and cemented with 140 sacks of cement. Circ. Job complete at 3:30 PM, July 15, 1967. No oil string was run. D. & A., plugged July 23, 1967.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>C. F. S.</u>
845	Shale & Shells	2931'
1045	Sand	2960'
1330	Shale & Shells	3095'
1367	Anhydrite	3115'
1800	Shale & Shells	3170'
1880	Shale & Lime Streaks	3190'
2805	Lime & Shale	3225'
3170	Lime	3245'
3412	Lime & Shale	3264'
3440	Lime, Shale & Sand	3275'
3467	Lime & Shale	3325'
3515	Lime & Chert, RTD	3350'
3514	Log Total Depth	3373'
		3399'
		3412'
		3434'
		3440'
		3467'
		3475'
		3483'

8/10/67

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1967

CONSERVATION DIVISION
Wichita, Kansas

Slope Tests
2000
2500
3000
3500

S. L. M.

Board 2994.08
Strap 2992.91
Diff. 1.17 long

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 3rd day of August, 1967, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

L. M. Whiting
L. M. Whiting, Notary Public

