

15-163-20042-00-00

~~15-163-20042-00-00~~

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rooks County, Sec. 3 Twp. 9S Rge. ~~(E)~~ 17 (W)

Location as "NE/CNW/SW" or footage from lines SW SE NW
Lease Owner Pickrell Drilling Company
Lease Name Hrabe "B" Well No. 3
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed Sept. 11 19 67
Application for plugging filed July 31 19 70
Application for plugging approved July 31 19 70
Plugging commenced August 1 19 70
Plugging completed August 4 19 70
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3507 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	214'	None
				4-1/2"	3505'	1515'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

August 1, 1970 Plugged off bottom. Dumped sand to 3350'. Mixed and dumped 4 sx of cement to 3300'.

August 4, 1970 Plugged off top. Globe Oil Well Cementing Co., Inc. mixed and pumped down 8-5/8" surface casing: 15 sx gel and 5 sx hulls, 70 sx of cement, 5 sx gel, released plug and mixed and pumped 50 sx of cement.

9/21/70
RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Russ Casing Pulling, Inc.
Address P. O. Box 1082, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dale M. Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale M. Robinson
705 Fourth National Bank Bldg, Wichita, Kansas
(Address)



Subscribed and sworn to before me this 18th day of September, 1970

Esther Lamone
Notary Public

My commission expires January 19, 1973

15-163-20042-00-00
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas 67202
Rotary Drilling Commenced 7/24/67

LOCATION: Hrabe "B" No. 3
SW SE NW Section 3-9S-17W
Rooks County, Kansas
Rotary Drilling Completed 8/1/67

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (10 jts.) 8 5/8" surface casing set at 213' and cemented with 125 sacks cement. (110 jts.) 4 1/2" casing set at 3405' and cemented with 160 sacks cement. Completed 8:40 AM, August 1, 1967.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

60	Top Soil & Clay	<u>C. F. S.</u>
191	Shale & Shells	2945
213	Shale	3105
795	Shale & Shells	3156
1025	Sand	3180
1324	Shale & Shells	3215
1359	Anhydrite	3230
1490	Shale & Shells	3248
1790	Shale	3260
1910	Shale & Lime Streaks	3337
2905	Shale & Lime	3363
3156	Lime	3388
3225	Lime & Shale	3403
3450	Lime	3426
3057	Lime & Shale, RTD	3450
3056	L.T.D.	3461
		3466
		3472
		3492
		3507

RECEIVED
STATE CORPORATION COMMISSION
AUG 3 1970
CONSERVATION DIVISION
Wichita, Kansas

8/3/70

Slope Tests
2500
3000

	<u>S. L. M.</u>
Board	2965.24
Strap	2964.26
Diff.	.98 long

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By *C. W. Sebitts* Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 10th day of August, 19 67, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

L. M. Whiting
L. M. Whiting Notary Public