


18-163-20678-0020

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rooks County, Sec. 4 Twp. 9S Rge. 17 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
SE SW SE  
Lease Owner Pickrell Drilling Company  
Lease Name Twin Mounds Unit D KCC Well No. D-55  
Office Address 205 Litwin Bldg., Wichita, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole) 67202



Locate well correctly on above  
Section Plat

D & A  
Date Well completed 19  
Application for plugging filed May 31 1977  
Application for plugging approved 19  
Plugging commenced June 3 1977  
Plugging completed June 9 1977  
Reason for abandonment of well or producing formation  
dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 3520  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASIN. RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			239'	8 5/8"	239'	none
			3518'	4 1/2"	3518'	2517.89

RECEIVED  
STATE CORPORATION COMMISSION  
6/16/77  
JUN 16 1977

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Sanded back to 3450' and dumped 3 sacks of cement.

Allied Cementing Company, Inc. plugged well pumping in 1 sack of hulls,  
25 sacks of gel and 100 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PIPE PULLERS, INC.  
Box 128, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON ss.  
Evelyn Roth

(employee of owner) or (owner or operator) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of June 1977

My commission expires

JENNY. KASSELMAN  
NOTARY PUBLIC  
BARTON COUNTY, KANSAS  
MY COMM. EXP. JULY 16, 1978

Jerry Kasselmann  
Notary Public.

15-163-20678-0000

Dup

**ROTARY DRILLING LOG**

COMPANY: PICKRELL DRILLING COMPANY  
205 LITWIN BLDG.  
WICHITA, KS. 67202  
LOCATION: TWIN MOUNDS UNIT "D" #5  
SE SW SE Sec. 4-9S-17W  
Rooks Co., Ks.

Rotary Drilling Commenced 2-1-77  
Rotary Drilling Completed 2-09-77

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
**Wichita, Kansas**

CASING RECORD: Surface casing set of 8 5/8" set at 237' with 150sx. Comp. 7:45PM 2-1-77  
4 1/2" casing set at 3518' w/75sx. Comp. 2-10-77

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Rock	60
Shale	239
Shale	700
Shale & Sand	1409
Shale	1444
Shale	1500
Shale & Lime	1885
Shale	2125
Shale & Lime	2335
Shale & Lime	2585
Shale & Lime	2795
Shale & Lime	2990
Lime & Shale	3125
Lime & Shale	3245
Shale	3315
Lime	3390
Lime	3405
Lime	3430
Lime	3489
Shale & Lime	3502
Lime	3520

6/29/77

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

**PICKRELL DRILLING COMPANY**  
By [Signature]  
Attorney-in-Fact  
C. W. Sebitts

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 22 day of June, 19 77, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires:



[Signature]  
Jo Ann Sarver Notary Public

15-163-20678-0000

WELL DATA  
TWIN MOUNDS UNIT WELL D-5

RTD: 3520'

Casing:

Surface: 8-5/8" @ 239'.

Long String: 4½", 10.5# Limited Service @ 3518' w/75sx. 50-50 Poz.  
w/10# Gilsonite/sx. plus 50sx. common.

PBTD: 3483' (Petro Log)

Perfs: 3472½ - 3476'

Top of Cement:

Theoretical: 2685'

Estimated: 2895' (Based on 75% fillup)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 01 1977

CONSERVATION DIVISION  
Wichita, Kansas

6/1/77