

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-20679 ⁰⁰

LEASE NAME Twin Mounds Unit C

WELL NUMBER 6-5 WIW 5 ^{KCC CAP}

4950 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 3 TWP. 9S RGE. 7 (EXX(W))

COUNTY Rooks

Date Well Completed 4/8/77

Plugging Commenced 6/27/88(*)

Plugging Completed 7/14/88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Pickrell Drilling Co., Inc.

ADDRESS 110 N. Market, Suite #205, Wichita, KS 67202

PHONE#(316) 262-8427 OPERATORS LICENSE NO. 5123

Character of Well WIW

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/28/88 (date)

by Shari Feist (Field rep. Dennis Hammel approved final field (KCC District Agent's Name) procedure.)

Is ACO-1 filed? yes If not, is well log attached? attached to application

Producing Formation Pleasanton Sand Depth to Top 3441 Bottom 3447 T.D. 3500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		-0-	236	8 5/8"	236	none
		-0-	3496	4 1/2"	3496	none

RECEIVED
 STATE CORPORATION COMMISSION
 7/28/88

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. N/A

Address Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack Gurley, Engineer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack Gurley

(Address) Jack Gurley, Engineer
 110 N. Market, Suite #205
 Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 27th day of July, 19 88

SUSAN KENDALL
 NOTARY PUBLIC
 STATE OF KANSAS
 My Comm. Exp. 10-6-91

Susan Kendall
 Notary Public
 Susan Kendall

(*)Operations began. Clean up around well and dig out braden head. Prepare well for P&A.
 Contact and communication with KCC representative had been going on for some time. Form CP-4
 Revised 07-87

PICKRELL DRILLING COMPANY, INC.

110 NORTH MARKET - SUITE 205

WICHITA, KANSAS 67202-1996

(316) 262-8427

July 26, 1988

15-163-20679-00-00
Twin Mounds Unit C 5 KCC
~~Twin Mounds C-5 WIW~~
NE NW NE Sec. 4-9S-17W
Rooks County, Kansas
P&A Well

RECEIVED
STATE CORPORATION COMMISSION

7/28/88 JUL 28 1988

CONSERVATION DIVISION
Wichita, Kansas

WELL DATA:

RTD: 3500'
4 1/2" 10.5# Casing w/125 sx @ 3496'
8 5/8" Surface w/140 sx @ 236'
Tops: Anhydrite 1370'-1405' (approx)
Base Dakota 785' (approx)
Elevation: 2026' G.L.
PBSD: 3460'
Perforations: 3443'-3446' (Pleasanton Sand)

6/27/88 Clean up around wellhead, dig out around braden head, prepare well for P&A.

7/13/88

12:05 p.m. Rig up Allied Cementing Co. Took injection rate down casing, 4 BPM @ 300 PSI. Mixed 120 sx 60/40 pozmix, 6% gel with 300#'s cotton seed hulls, follow w/swiper plug & displaced plug to 1400'. Shut casing in w/150 PSI. Will perforate and finish in a.m.

7/14/88

Rig up Electra Logging. Logger found plug @ 1423'. Perforate 1370'-1373' (3 ft. 2 holes/ft.) Perforate 800'-803' (3 ft. 2 holes/ft.) Rig up Allied Cementing Co. Mixed 100 sx ATL 1/4#/sk Floseal down casing w/150# cotton seed hulls-shut in @ 200 PSI. Mixed 50 sx ATL 1/4#/sk Floseal w/150#'s cotton seed hulls. Shut in @ 400 PSI.

Witnessed by Dennis Hammel KCC representative.

Plugging complete

Ed Mondero
Ed Mondero

EM:JG/slk