

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22,633-0000

LEASE NAME Diehl

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4950 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 4 TWP. 9 RGE. 17W (E) or (W)

COUNTY Rooks

Date Well Completed 05-85

Plugging Commenced 07-15-97

Plugging Completed 07-15-97

LEASE OPERATOR Palomino Petroleum, Inc.

ADDRESS 4924 SE 84th Street, Newton, Kansas 67114

PHONE# (316) 283-0232 OPERATORS LICENSE NO. 30742

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 07-15-97 (date)

by Rich Williams District 4 office (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? No

Producing Formation L/K C Depth to Top 3420 Bottom 3425 T.D. 3529

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	260	8 5/8"	260	-0-
	Production		3529	4 1/2"	3529	250'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Bottom plug- sand and cement to 3370'. Allied mixed 40 sacks cement @ 1325-1875', 50 sacks and 100# hulls 950-700, circulated cement @ 200' with 75 of cement and 400# hulls and filled cellar.
Time started 10:00 am, completed 2:00 pm

Name of Plugging Contractor D. S. & W. Well Servicing, Inc. License No. 6901

Address P. O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Klee Watchous

STATE OF Kansas COUNTY OF Barton, ss.

Arthur P. Strube (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well as filed the
the same are true and correct, so help me God.


(Signature) Arthur P. Strube

(Address) P. O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 24 day of July, 1997

Bonnie L. Connell
Notary Public

My Commission Expires: April 8, 2001
USE ONLY ONE SIDE OF EACH FORM



Form CP-4
Revised 05-88