

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-03205-06 20
API NUMBER Compl 6/55
LEASE NAME Thompson
WELL NUMBER 4
1650 Ft. from S Section Line
4950 Ft. from E Section Line

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc.
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606
Character of Well Oil (Oil, Gas, D&A, SWD, Input, Water Supply Well)

SEC. 5 TWP. 9 S RGE. 17W (E) or (W)
COUNTY Rooks
Date Well Completed 6/55
Plugging commenced 11/13/97
Plugging Completed 11/13/97

The plugging proposal was approved on _____ (date)
by _____ (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ TD _____

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put	Pulled out
				8 5/8	214	
				5 1/2	3407	

11/24/97

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Perf 1820-1323-866, ran tbg to 2939', pumped 100 sx 60/40 Poz, 10% gel, 200# hulls, spotted w/6 BFW. Pulled tbg to 1600', pumped 100 sx 60/40 Poz, 10% gel, 200# hulls. Pulled tbg to 300', pumped 35 sx 60/40 Poz to circ to surface. TOH w/tbg. Tied onto 5 1/2 csg, pumped 10 sx. Max 500#. ISIP 200#. Tied onto 8 5/8, pumped 10 sx w/100# hulls. Max 400#, ISIP 100#. JC.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606
Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK .SS.
Larry M. Jack, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry M Jack
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 22 day of November, 1997

Kerran Redington
Notary Public - Kerran Redington

My Commission Expires: 2/6/98

