

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-19024-00-02
LEASE NAME J.H. THOMPSON

WELL NUMBER 2

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

330/650 Pt. from S Section Line
4950/3620 Pt. from E Section Line

RECEIVED
MAY 28 2002
KANSAS
WICHITA

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 5 TWP. 9S RGE. 17W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY ROOKS
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 4/27/55
Character of Well Oil (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 5/21/02
Plugging Completed 5/21/02

The plugging proposal was approved on 5/21/02 (date)
by Pat Staab w/KCC Hays, KS. (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no
Producing Formation Arbuckle Depth to Top 3133 Bottom 3382 OA TD 3435'

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	208	8 5/8	372	0
		production	3425	5 1/2	4267	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Perforated 5 1/2" csg @ 1800' & 1340'. 2SPF. RIH w/ 2 3/8" tbg. to 2103'. Pumped 100 sxs 60/40 poz. 10% gel. 300# hulls. Pulled tbg. to 1050'. Pumped 95 sxs & 200# hulls to circ cmt. to surface. TOH w/tbg. Tied onto 5 1/2" csg. Pumped 130 sxs. 800# max press 350# ISIP. Tied onto 8 5/8". Pressured to 500# & held Well P/A. Witnessed and approved by Pat Staab w/ KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK .SS.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 22 th day of May 2002

Notary Public - Barbara J. Dodson
My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



OK

ALLIED CEMENTING CO., INC.

10671

Federal Tax I.D.# XXXXXXXXXX

SHIP TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: R

15-163-19024-00-00

DATE <u>5/21/02</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>10:20 A.M.</u>	JOB START	JOB FINISH <u>12:30 P.M.</u>
LEASE <u>Thompson</u>	WELL # <u>2</u>	LOCATION <u>P.V. 112 30 1/2 E 10 1 E</u>			COUNTY <u>Rooks</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)		<u>1/2 N E INTO</u>					

CONTRACTOR Martin

TYPE OF JOB OHF

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH _____

TUBING SIZE 2" DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED 325 60/40 1070 Grel

5 HULLS

COMMON	<u>195</u>	@	<u>665</u>	<u>1296 75</u>
POZMIX	<u>130</u>	@	<u>355</u>	<u>461 50</u>
GEL	<u>22</u>	@	<u>10 00</u>	<u>220 00</u>
CHLORIDE		@		
<u>Hulls</u>	<u>5</u>	@	<u>18 00</u>	<u>90 00</u>
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>325</u>	@	<u>110</u>	<u>357 50</u>
MILEAGE		@	<u>44/SK/Mile</u>	<u>390 00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Paul

122 HELPER Darin

BULK TRUCK

362 DRIVER Brent

BULK TRUCK

_____ DRIVER _____

RECEIVED

MAY 28 2002 5/28/02

KCC WICHITA SERVICE

TOTAL 2815 75

REMARKS:

Top @ 2041. spot 1005x w/ 3 Hulls

1000' Circ. Cement w/ 955c

and 2 Hulls.

5 1/2 csg. Top off w/ 305x. press to

500psi. Shut in 200psi.

Annulus 500psi.

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 175 00

EXTRA FOOTAGE _____ @ _____

MILEAGE 30 @ 3 00 90 00

PLUG _____ @ _____

_____ @ _____

_____ @ _____

CHARGE TO: Martin

STREET _____

CITY _____ STATE _____ ZIP _____

TOTAL 565 00

FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

done to satisfaction and _____

contractor. I have read & understand the "TERMS AND

CONDITIONS" listed on the reverse side.

A I L

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

15-163-19024-00-00

ALLIED CEMENTING CO., INC.

P.O. BOX 31
RUSSELL, KS 67665
PH (785) 483-3887
FAX (785) 483-5566
FEDERAL TAX ID# [REDACTED]

RECEIVED
MAY 28 2002
KCG WICHITA

RECEIVED
MAY 24 2002

* I N V O I C E *

Invoice Number: 087233
Invoice Date: 05/22/02

5/28/02

Sold Murfin Drilling Co.
To: 250 N. Water, St. #300
Wichita, KS
67202

Cust. I.D.: Murfin
P.O. Number: Thompson #2
P.O. Date: 05/22/02
Due Date: 06/21/02
Terms: Net 30
36 R/A/RK

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	195.00	SKS	6.6500	1296.75	T
Pozmix	130.00	SKS	3.5500	461.50	T
Gel	22.00	SKS	10.0000	220.00	T
Hulls	5.00	SKS	18.0000	90.00	T
Handling	325.00	SKS	1.1000	357.50	T
Mileage (30)	30.00	MILE	13.0000	390.00	T
325 sks @\$.04 per sk per mi					
Plug	1.00	JOB	475.0000	475.00	T
Mileage pmp trk	30.00	MILE	3.0000	90.00	T

All Prices Are Net, Payable 30 Days Following
Date of Invoice. 1 1/2% Charged Thereafter.
If Account CURRENT take Discount of \$ 338.08
ONLY if paid within 30 days from Invoice Date

Subtotal: 3380.75
Tax: 216.37
Payments: 0.00
Total: 3597.12

15-163-19024-0000

Sunray Oil Corporation
Tulsa, Oklahoma

Tulsa, Oklahoma
May 2, 1955

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: April 17, 1955
Drilling Completed: April 27, 1955

J. H. Thompson #2 SW/4
Section 5-9S-17W, Rooks
County, Kansas.

DRILLERS LOG

RECEIVED
APR 16 2002
KCC WICHITA
4/16/02

Shale	0-210
Shale & Shells	210-905
Sand	905-1030
Red Bed	1030-1325
Anhydrite	1325-1370
Shale & Shells	1370-1795
Broken Lime, & Shale	1795-1970
Shale & Lime	1970-2200
Lime Broken	2200-2350
Lime & Shale	2350-2645
Shale & Lime	2645-2740
Lime	2740-2790
Broken Lime	2790-2900
Lime & Shale	2900-3005
Lime	3005-3180
Lime K.C.	3180-3250
Lime	3250-3420
Conglomerate	3420-3423
Arbuckle	3423-3433 TD

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Oil Corporation's J. H. Thompson #2 SW/4 Section 5-9S-17W, Rooks County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1956
My Commission Expires