


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-163-00717-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rocks _____ County. Sec. 6 Twp. 9 Rge. _____ (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines NE/NE/SW
Lease Owner Morganstern & Spector
Lease Name Moos Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 5-24-54 19____
Application for plugging filed February 19, 1956 19____
Application for plugging approved February 20, 1956 19____
Plugging commenced 3/2-56 19 56
Plugging completed 3-6-56 19 56
Reason for abandonment of well or producing formation failure to produce profitably
If a producing well is abandoned, date of last production February, 1956 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3387 Bottom 3391 Total Depth of Well 3391 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4" OD	157'	None
				5 1/2" OD	3387'	2602.48'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging started 3-1-56 and completed 3-6-56. Plugged off bottom with sand back to 3290' and dumped in 4 sacks of cement with bailer. Shot casing off at 2612' and pulled casing out of hole. Plugged well as follows: Filled hole with heavy mud to 152'; set permanent rock bridge; and dumped in 20 sacks of cement. Filled hole with heavy mud to 30' of top; set permanent rock bridge; and dumped in 10 sacks of cement for cap on well.

RECEIVED
3/14/56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. FORBES d/b/a FORBES CASING PULLING CO.
Address P. O. BOX 221, GREAT BEND, KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.
Morganstern & Spector (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Morganstern & Spector
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of March, 19 56

My commission expires Dec 1, 1959 Elice Coady Notary Public.

PLUGGING
FILE SEC 6 T 9 R 17W
BOOK PAGE 39 LINE 30

15-163-00717-00-22
 WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- UNITED DRILLING, INC.
 Farm- Moos No. 1

SEC. 6 T. 9 R. 17W
 NE NE SW

Total Depth. 3391'
 Comm. 5-14-54 Comp. 5-24-54
 Shot or Treated.
 Contractor.
 Issued. 7-31-54

County Rooks

KANSAS



CASING:
 10 3/4" 152'

Elevation. 1973'

Production. 25 BOPD

Figures Indicate Bottom of Formations.

postrock-sand-shale	75
shale	110
shale-sand-red bed	385
anhydrite	1290
shale	1330
shale-lime shells	1550
shale-shells	1740
lime	2085
shale-lime	2210
shale-shells	2400
lime-shale	2470
lime	2935
lime-shale	3240
lime	3290
lime	3391
Total Depth	

TOPS: Scout	
Heebner	3088
Toronto	3110
Lansing	3127

2/25/56

RECEIVED
 STATE CORPORATION COMMISSION

FEB 20 1956

REGISTRATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 6 T. 9 R. 17W
 BOOK PAGE 39 LINE 30