

15-163-01488-0002

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 8-3-1955  
LEASE NAME MOOS  
WELL NUMBER 4  
SPOT LOCATION SE NE SE  
SEC. 6 TWP. 9S RGE. 17 (E) or (W) (W)  
COUNTY Rooks  
Date Well Completed 8-3-55  
Plugging Commenced 9-17-85  
Plugging Completed 9-17-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR OKMAR OIL COMPANY  
ADDRESS 970 4th Financial Center, Wichita, KS 67202

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5245

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6 (Hays)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Arbuckle Depth to top 3407 bottom 3424 T.D. 3424'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3405	3424	8 5/8"	104'	0
Kansas City	Water	3139	3326	5 1/2"	3407'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. PI 125 sx Pozmix cement w/10% gel down 5 1/2" casing & 100 sx Pozmix cement w/10% gel down the 5 1/2" and 8 5/8" annulus.


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sun Cementing License No. NA  
Address Box 169, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.

David Munro (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David Munro  
(Address) 970 4th Financial Ctr, Wichita



SUBSCRIBED AND SWORN TO before me this 14th day of October, 1985

Cecelia A. Bowser  
Notary Public

My Commission expires: August 5, 1987

STATE CORPORATION COMMISSION

10/15/85

OCT 15 1985

Form CP-4 1-84  
Revised 06-83

# McWilliams & Steincamp

Petroleum Geologists

McBride Building

Great Bend, Kansas

August 4, 1955

15-163-01488-00-20

Sidey Oil Company  
#4 Moos  
SE NE SE Sec. 6-9s-17w  
Rocks County, Kansas

Elevation: 1988' KB

8-5/8" surface casing set and cemented at 104' with 100 sacks cement.

Top Anhydrite 1290'

1978  
1290  
678

Top Heebner 3096' (-1108')

Top Toronto 3121' (-1133')

Top Lansing 3139' (-1151')

3174-78 Limestone white, fine crystalline, poor pin-point porosity, spotted stain, no odor.

3211-19 Limestone white, fine crystalline, poor pin-point porosity, trace spotted stain, no odor.

3223-26 Limestone white, oolitic and oolitic, poor to fair porosity, spotted to fair saturation, no odor.

3236-40 Limestone same.

3257-60 Limestone white, fine crystalline, poor vugular porosity, spotted saturation, no odor.

3320-26 Limestone cream, medium crystalline, slightly oolitic and oolitic, poor to fair porosity, spotted to fair saturation, no odor.

Top Arbuckle 3405' (-1117')

3405-08 Dolomite white, medium crystalline, poor inter-crystalline porosity, slight show of free oil, faint odor.

Rotary Total Depth 3408'.

5 1/2" O.D. casing set and cemented at 3407' with 100 sacks cement.

McWILLIAMS & STEINCAMP

RECEIVED  
STATE CORPORATION COMMISSION

SEP 9 1955

CONSERVATION DIVISION  
Wichita, Kansas

*Charles W. Steincamp*

CHARLES W. STEINCAMP

CWS:mjk

9/6/55