


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-163-02279-0000  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks \_\_\_\_\_ County. Sec. 6 Twp. 9 Rge. 17 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner Petroleum, Inc.  
Lease Name Gouldman Well No. 2  
Office Address Route 2, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed July 18, 1954  
Application for plugging filed June 17, 1959  
Application for plugging approved June 19, 1959  
Plugging commenced June 19, 1959  
Plugging completed June 23, 1959  
Reason for abandonment of well or producing formation Depletion of  
Producible Zones  
If a producing well is abandoned, date of last production May 27, 1959  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas  
Producing formation Kansas City Depth to top 3137 Bottom --- Total Depth of Well 3400 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	202'	None
				5-1/2"	3396'	2450'
Kansas City	Water and Little Oil	3353'	3356'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

(Plugged back to 3398.50')

Filled hole with crushed rock from 3398.50' to 3340'. Placed 1/2 sacks cement on top of rock at 3340'. Pulled 60 joints of casing. Ran plug to 570' and pumped in 26 sacks commercial gel. Broke circulation and placed 20 sacks cement on top of mud. Pulled 13 joints of casing and ran 20 sacks cement. Pulled the remaining 6 joints of casing and ran 10 sacks cement to the base of well cellar.

RECEIVED  
STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

JUL 2 1959

JUN 26 1959

CONSERVATION DIVISION  
Wichita, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

6/26/59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service  
Address 102 West 18th Street, Hutchinson, Kansas.

STATE OF KANSAS, COUNTY OF BARTON, ss.  
DON SEARLE (employee of owner) or (OWNER OR OPERATOR) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

ROUTE 2, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of June, 19 59

Arthur J. Wiles

My commission expires April 14, 1963

Notary Public.

PLUGGING  
FILE SEC. 8 T. 30 R. 1E  
BOOK PAGE 46 LINE 37

# WELL LOG

15-163-02279-0000

COMPANY Petroleum, Inc.

SEC. 6 T. 9 R. 17W

FARM GOULDMAN

NO. 2

LOC. SE SE NW


TOTAL DEPTH 3400'

COUNTY Rooks County, Kansas

COMM. June 27, 1954

COMP. July 8, 1954

CONTRACTOR Garvey Drilling Company



CASING 8-5/8" @ 202' w/125' sax.  
5 1/2" @ 3396' w/100' sax.

ELEVATION 1983 R.B.

PRODUCTION Arbuckle

FIGURES INDICATE BOTTOM OF FORMATIONS

60	Rock & Clay
845	Shale & Shells
970	Sand
1312	Shale & Shells
1350	Anhydrite
1740	Shale & Shells
2905	Lime & Shale
2970	Lime
3020	Lime & Shale
3400	Lime
3400	R.T.D.

Tops:

Heebner:	3096 (-1113)
Toronto:	3117 (-1134)
Lansing:	3137 (-1154)
Arbuckle:	3394 (-1411)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 1 1959

CONSERVATION DIVISION  
Wichita, Kansas

7/1/59

PLUGGING  
FILE SEC. 6 T. 9 R. 17W  
BOOK PAGE 46 LINE 37

State of KANSAS  
County of SEDGWICK

ss:

I, W. W. Fisher of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the GOULDMAN #2 well.

W W Fisher

Subscribed and sworn to before me this 13th day of July 19 54

My Commission Expires: October 13, 1954

Charlotta Meidman  
NOTARY PUBLIC