


15-113-02806-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Rooks County. Sec. 6 Twp. 9 Rge. 17 (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW NE SW  
Lease Owner United Drilling, Inc.  
Lease Name Moos Well No. 2  
Office Address Mohl Bldg., Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed July 31, 1954 19  
Application for plugging filed July 31, 1954 19  
Application for plugging approved July 31, 1954 19  
Plugging commenced July 31, 1954 19  
Plugging completed July 31, 1954 19  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. E. R. Petty  
Producing formation Depth to top Bottom Total Depth of Well 3422 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with rotary mud from 3422' to 155'; from 155' to 120' with Halliburton plug; 1/2 sack hulls, and 15 sacks cement through drill pipe; from 120' to 40' with rotary mud; from 40' to -0- with Halliburton plug, 1/2 sack hulls, and 10 sacks cement.

Job completed at 5 P.M. July 31, 1954

RECEIVED  
STATE CORPORATION COMMISSION

AUG 22 1954

CONSERVATION DIVISION  
Wichita, Kansas

8/22/54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor  
Address

STATE OF Kansas, COUNTY OF Russell, ss.  
Joan Hanes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joan Hanes  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of August, 1954

My commission expires 10-30-57  
Mylene Zook Notary Public.

PLUGGING  
FILE SEC 6 T 9 R 17 W  
BOOK PAGE 53 LINE 15

15-163-02806-0000

W E L L L O G

Moos #2

United Drilling, Inc.

NW NE SW, Section 6-9-17  
Rooks County, Kansas

Commenced: July 21, 1954  
Completed: July 31, 1954

Production: Dry Hole

Casing Record:  
8 5/8" set at 159 feet.

-----

Depth	Formation
50 feet	Sand
159 "	Shale and sand
1020 "	Redbed
1310 "	Anhydrite
1350 "	Shale and shells
2010 "	Lime and shale
2360 "	Shale
2370 "	Shale and lime
2565 "	Shale and shells
2860 "	Shale and lime
2940 "	Lime
3105 "	Lime and shale
3155 "	Lime
3344 "	Lime and shale
3398 "	Lime and conglomerate
3422 "	Total Depth

I hereby certify that the above information is true and correct to the best of my knowledge.

Joan Hanes  
Joan Hanes, Secretary to  
Clyde G. Kissinger, Pres.

Subscribed and Sworn to before me this 2nd day of August, 1954.

Marlene Zisk  
Notary Public

My Commission Expires: 10-30-57

**PLUGGING**  
 FILE SEC 6 T 9 R 17W  
 BOOK PAGE 53 LINE 15

8/16/54  
**RECEIVED**  
 STATE DEPARTMENT  
 CONSERVATION DIVISION  
 WASHINGTON, D.C.