


15-163-03118-0500

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Russell County. Sec. 6 Twp. 9 Rge. 17 (E)W (W)
Location as "NE/CNW/SW" or footage from lines NW/4 NW/4 NE/4
Lease Owner V.D. Sidey Oil Company, Russell, Kansas.
Lease Name Sidey Oil Co- Garvert Well No. 2
Office Address Russell, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced April 13 19 53
Plugging completed April 28 19 53
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3416 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3416 feet to surface feet for each plug set.

Hole filled with sand from 3416 ft. to 3410 ft; five sacks of cement placed in hole with dump bailer to form cement plug from 3410 to 3370; hole filled with mud from 3370 to 150 ft; fifty sacks of cement pumped in hole by Halliburton pump truck from 150 feet to top of surface pipe, forming solid cement plug from top of surface pipe down to 150 feet.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnes and Sons Pipe Pulling Co.,
Address Russell, Kansas.

STATE OF _____, COUNTY OF _____, ss.
_____(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 387 Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of April, 1953

[Signature]
Notary Public.

My commission expires Sept 17, 1956

24-2675-S 2-52-20M
PLUGGING
FILE SEC 6 T 9 R 17W
BOOK PAGE 93 WIG 5

STATE CORPORATION COMMISSION
MAY 1 1953
CONSERVATION DIVISION
Wichita, Kansas
5/1/53

15-163-03118-0000

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY V. D. Sidey Oil Co.


SEC. 6 T. 9 R. 17W

FARM Garvert NO. 1

LOC. NW NW NE

TOTAL DEPTH 3417
COMM. 2-8-51 COMP. 2-22-51
SHOT OR TREATED
CONTRACTOR Murfin Drilling Co.
ISSUED

COUNTY Rooks



CASING
20 10
15 1/2 8 1/4 103
12 1/2 6 1/2
13 1/2 5 1/4 3413

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

110 shale & shells	3090 lime
250 gray shale	3115 lime & shale
410 shale & shells	3136 lime
430 shale & lime shells	3141 shale
560 shale & shells	3163 lime
590 gray shale & sand	3180 shale & lime
740 shale & shells	3187 lime
775 sand	3194 shale
828 shale & shells	3411 lime
932 sand	3417 Arb.
940 shale	
995 sand	
1115 red rock & shale	
1286 red bed & shale	
1320 Anhydrite	
1630 shale & shells	
1745 salt & shale	
1860 shale & shells	
1870 lime & shale	
2055 broken lime	
2080 lime	
2165 broken lime	
2250 lime	
2375 shale & lime	
2430 lime	
2630 shale & lime	
2720 shale & lime shells	
2865 lime & shale	
2875 shale	
2890 shale & lime	
2903 lime	
2932 shale & lime	
2965 lime	
3035 lime & shale	

4/14/53

STATE OF KANSAS)
) SS:
SEDGWICK COUNTY)

I, W. R. Murfin, of the Murfin Drilling Co., upon oath state that the above and foregoing is a true and correct copy of the log of the No. 1 Garvert well.

W. R. Murfin
W. R. Murfin

Subscribed and sworn to before me this 28th day of February, 1951.

Gesseline Hayes
Notary Public

My Commission Expires: 3-5-52

PLUGGING
FILE SEC. 6 T. 9 R. 17W
BOOK PAGE 93 LINE 5