

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-07206-0050
API NUMBER 6-15-1954

LEASE NAME MOOS

WELL NUMBER 2

SPOT LOCATION NW NW SE

SEC. 6 TWP. 9S RGE. 17 (E) or (W) (W)

COUNTY Rooks

Date Well Completed 6-15-54

Plugging Commenced 9-18-85

Plugging Completed 9-18-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR OKMAR OIL COMPANY

ADDRESS 970 4th Financial Center, Wichita, KS 67202

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5245

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6 (Hays)

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Kansas City Depth to top 3110 bottom 3328 T.D. 3383'
Arbuckle 3360 3383

Show depth and thickness of all water, oil and gas formations. NOTE: Cement squeezed @ 941'

OIL, GAS OR WATER RECORDS | CASING RECORD w/200 sx cement.

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3358	3383	10 3/4"	110'	0
Kansas City	Oil	3109	3332	7"	3367'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. PI 325 sx 60/40 Pozmix cement w/10% gel down the 7" casing and 50 sx Pozmix cement w/10% gel down the 10 3/4" & 7" casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sun Cementing License No. NA
Address Box 169, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.

David Munro (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David Munro

(Address) 970 4th Financial Ctr, Wichita


CECELIA A. BOWSER
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 8/5/87

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1985

Cecelia A. Bowser
Notary Public

My Commission expires: August 5, 1987

RECEIVED
STATE CORPORATION COMMISSION

10/15/85

OCT 15 1985

Form CP-4 1-84
Revised 06-83

SIDEY DRILLING COMPANY

BUILDING & LOAN BLDG.

P. O. BOX 387

RUSSELL, KANSAS

15-163-03206-00-00

COMPANY V. D. Sidey Oil Company

SEC. 6 T. 9S R. 17W

FARM Moos

NO. 2

LOC. NW NW SE

TOTAL DEPTH 3364'

COMM. 6-14-54

COMP. 6-24-54

COUNTY Rooks

SHOT OR TREATED

CONTRACTOR Sidey Drilling Company

ISSUED

	CASING		
20	10	91'	
15½	8¾		
12½	6¾	3492'	
13%	5 5/16		

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0-25	Shale
25-30	Sand
30-480	Shale & shells
480-520	Sand
520-725	Shale & sand
725-760	Sand
760-805	Shale & shells
805-840	Shale & shells
840-980	Sand
980-1267	Red bed
1267-1295	Anhydrite
1295-1303	Anhydrite
1303-1700	Shale & shells
1700-1740	Lime & shale
1740-1910	Shale & lime shells
1910-2150	Lime & shale
2150-2215	Lime
2215-2870	Lime & shale
2870-3290	Lime
3290-3355	Lime
3355-3364	Lime & shale RTD

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

I, V. D. Sidey, of the Sidey Drilling Company, upon oath states that the above and foregoing is a true and correct copy of the log on the Moos #2 Well.

V. D. Sidey

Subscribed and sworn to before me this 6th day of July, 1954.

NOTARY PUBLIC

My commission expires: September 17, 1956

RECEIVED
STATE CORPORATION COMMISSION

SEP 6

9/6/55

CONSERVATION DIVISION
Wichita, Kansas