

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-163-23,090-00-00

LEASE NAME MURPHY

WELL NUMBER #1

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 25 TWP. 9 RGE. 16 ~~XXXX~~ (W)

COUNTY Rooks

Date Well Completed 5-24-90

Plugging Commenced 6-14-90

Plugging Completed 6-19-90

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR The Gene Brown Company

ADDRESS Drawer #220 Plainville, Kansas 67663

PHONE# (913) 434-4811 OPERATORS LICENSE NO. 5635

Character of Well non-productive  
 (Oil, Gas, D&A SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-07-90 (date)  
 by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation dry Depth Surface to Bottom T.D. 3584'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

CONSERVATION DIVISION

| Formation   | Content     | From | To   | Size  | Put In | Pulled out |
|-------------|-------------|------|------|-------|--------|------------|
| surface     | fresh water | 0    | 225  | 8 5/8 | 225    | none       |
| 1 KC -cong. | lime        | 0    | 3624 | 5 1/2 | 3624   | 2006       |
|             |             |      |      |       |        |            |
|             |             |      |      |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
A column of sand was placed from 3584 to 2940. Then 5 sacks cement were placed on top of sand at 2940. Pipe was shot off at 2006. 200 sacks 65-35 pozimix with 10% gel - 1/4# Flocele and 5 sacks hulls were pumped down 8 5/8 at 800 psi max pressure. Shut in pressure was 300 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address Hays, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Gene Brown Company

STATE OF Kansas COUNTY OF Rooks, ss.

Thomas M. Brown (Employee of Operator) ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas M Brown

(Address) Plainville, Kansas 67663

SUBSCRIBED AND SWORN TO before me this 16<sup>th</sup> day of July, 19 90

Kathy A. Wise  
 Notary Public

Commission Expires: May 27, 1990

