


15-163-01070-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Rooks \_\_\_\_\_ County. Sec. 26 Twp. 9 Rge. 16 (E) \_\_\_\_\_ (W) X  
Location as "NE/CNW%SW%" or footage from lines NE SW SW  
Lease Owner Leo J. Dreiling Oil Company  
Lease Name Reece Well No. 1  
Office Address Victoria, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D. & A.  
Date well completed 2/19/64 19  
Application for plugging filed 2/10/64 19  
Application for plugging approved 2/10/64 19  
Plugging commenced 2/10/64 19  
Plugging completed 2/10/64 19  
Reason for abandonment of well or producing formation -0-

If a producing well is abandoned, date of last production -0- 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 3620 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	150'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Rotary mud was used to fill hole to a depth of 450' were 1st plug was set using 20 sacks cement, filling hole to a depth of 150' were 2nd plug was set using 20 sacks cement, 3 rd plug was set at 40' using 10 sacks cement and filling hole to surface.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 2 1964

CONSERVATION DIVISION  
Wichita, Kansas

3-2-64

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.  
Address Victoria, Kansas

STATE OF Kansas COUNTY OF Ellis, ss.  
I, Leo F. Dreiling a partner (Employee of Owner) or (Owner) or (Operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling  
LEO F. DREILING

SUBSCRIBED AND SWORN to before me this 28th day of February, 19 64

My commission expires August 14, 1965

Ronald Zimmerman  
Notary Public.

15-103-01070-00-00

L. J. DREILING and SONS, Inc.  
VICTORIA, KANSAS

WELL LOG

Company	Leo J. Dreiling Oil Company Victoria, Kansas	Sec. 26	Twp. 9	Rng. 16
Farm	Reece No. 1	Location	NE SW SW	
Total Depth	3620'	County	Rocks County	
Comm.	2/4/64	Comp.	2/10/64	Elevation: D. F.
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas			G. R.
	Casing Record	Cement Record	Production:	
	8 5/8" - - - - 150'	100 sacks cement	D. & A.	

Figures Indicate Bottom of Formations

0 - 50	Surface Clay
50 - 150	Rock & Shale
150 - 500	Shale
500 - 1242	Shale
1242 - 1256	Anhydrite
1256 - 1276	Anhydrite
1276 - 1825	Shale & Shells
1825 - 2110	Shale & Lime
2110 - 2272	Shale & Lime
2272 - 2418	Lime & Shale
2418 - 2630	Shale
2630 - 2848	Shale
2848 - 3000	Shale & Lime
3000 - 3150	Lime
3150 - 3218	Lime
3218 - 3271	Lime
3271 - 3333	Lime
3333 - 3402	Lime
3402 - 3512	Lime
3512 - 3599	Lime
3599 - 3620	Lime
3620	TD

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 2 1964  
3-2-64  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF ELLIS )

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Reece No. 1.

Leo F. Dreiling  
LEO F. DREILING

Subscribed and sworn to before me this 18th day of February, 1964.

Ronald Zimmerman  
NOTARY PUBLIC

My Commission Expires: August 14, 1965