

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-163-00979-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rooks County, Sec. 28 Twp. 9 Rge. 16 (E) (W)

NORTH

		*	

Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_  
Lease Owner Dunlavy, Ginapp and Crow  
Lease Name Wells A Well No. 1  
Office Address P. O. Box 288 North Platte, Nebraska  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed September 29 19 56  
Application for plugging filed September 29 19 56  
Application for plugging approved September 29 19 56  
Plugging commenced September 29 19 56  
Plugging completed September 29 19 56  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3600 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface casing		0	161	8 5/8	161	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy mud to 155'. Set plug.  
Put in 1/3 sack hulls and 15 sacks cement.  
Filled with heavy mud to 40'. Set plug.  
Put in 1/3 sack hulls and 10 sacks cement.  
Wired with two wires.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor A. L. Jackson Drilling Company  
Address P. O. Box 194 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
A. L. Jackson, drilling contractor on (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Jackson  
P. O. Box 194 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of October, 19 56

My commission expires May 9, 1959

Notary Public.

PLUGGING  
FILE SEC 28 T 9 R 16  
BOOK PAGE 104 LINE 1

RECEIVED  
OCT 8 1956  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

10/8/56

15-163-00979-0006

Well Log  
Wells A - 1  
NW NE 28-9-16  
Rocks County, Kansas

0 - 145	Surface clay, sand and shells
145 - 160	Lime and shale
160 - 760	Shale
760 - 1280	Shale, shells and sand
1280 - 1320	Anhydrite
1320 - 1510	Shale and shells
1510 - 1890	Lime and shale
1890 - 1985	Lime
1985 - 2210	Lime and shale
2210 - 2430	Lime
2430 - 2465	Shale and lime
2465 - 2510	Lime and shale
2510 - 2655	Lime
2655 - 2880	Lime and shale
2880 - 2985	Shale and brown lime
2985 - 3094	Lime
3094 - 3140	Shale and lime
3140 - 3503	Lime
3503 - 3565	Lime and conglomerate
3565 - 3600	Lime and conglomerate - cherty
3600	T. D.

STATE OF KANSAS

COUNTY OF BARTON ss

A. L. Jackson, owner of A. L. Jackson Drilling Company, being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

A. L. Jackson  
A. L. Jackson

Subscribed and sworn before me this 2nd day of October, 1956.

Dick B. Evans  
Dick B. Evans  
Notary Public Barton County

My commission expires May 9, 1959

10/8/56

PLUGGING			
FILE	SEC 28	T 9	R 16 <sup>W</sup>
BOOK	PAGE 104	LINE 1	