

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

15-163-02803-0500

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Rooks County. Sec. 29 Twp. 9 Rge. 16 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines NE NE NE 1/2  
Lease Owner Trans Era Petroleum, Inc.  
Lease Name Jones Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 8/9/54 19  
Application for plugging filed 8/8/54 19  
Application for plugging approved 8/8/54 19  
Plugging commenced 8/9/54 19  
Plugging completed 8/9/54 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3599 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	160'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Finished laying down drill pipe. Filled hole with heavy mud to 150', set bottom plug at 150' with one-half sack of hulls and fifteen sacks of cement mixed and run through drill pipe. Filled hole with mud to 40', set top plug at 40' with one-half sack of hulls and ten sacks of cement used.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Trans Era Petroleum, Inc.  
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
H. R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Michaelis  
Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 54

My commission expires 1-30-57.

Margie Cooper  
Notary Public.

PLUGGING  
FILE SEC 29 T 9 R 16W  
BOOK PAGE 55 LINE 19

15-163-02803-00-00

Trans Era Petroleum, Inc.  
Jones #1

NE NE NE 29-9-16  
Rooks County, Ks.

Total Depth: 3599'  
Comm. 7/27/54  
Comp. 8/9/54

Casing

8 5/8" Set @ 160'

Cement

130 sacks of Bulk

FORMATION	DEPTH
Surface soil-clay	40
Clay-shells	70
Clay-shale	160
Shale	520
Shale-shells	765
Shale-sand streaks	980
Red bed-shale	1285
Anhydrite	1320
Shale	1425
Sand-shale	1525
Shale	1790
Lime-shells-shale	1960
Shale-lime	3265
Lime	3391
Lime-shale	3485
Lime	3530
Lime-shale-chert	3599'

STATE OF KANSAS }  
RUSSELL COUNTY } ss

I hereby certify that the above information is true and correct to  
the best of my knowledge.

*Cara Betz*

Subscribed and sworn to before me this 11th day of August, 1954.

*Margie Cooper*  
Notary Public

My commission expires: 1-30-57.

PLUGGING  
FILE DEC 29 1954  
BOOK PAGE 55 LINE 19

RECEIVED  
OCT 1 1954

8/13/54