

15-163-00485-007-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Rocks ..... County. Sec. 33. Twp. 25. Rge. 16W(E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines... S.E.S.E.-S.W

Lease Owner... Herndon H. 19

Lease Name... Conger Well No. 1

Office Address... Tulsa Okla

Character of Well (completed as Oil, Gas or Dry Hole)... Dry Hole

Date well completed... 7-3-53 19

Application for plugging filed... 7-3-53 19

Application for plugging approved... 7-3-53 19

Plugging commenced... 7-3-53- 19

Plugging completed... 7-3-53- 19

Reason for abandonment of well or producing formation.....

If a producing well is abandoned, date of last production..... 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well... Mr. Eldon Petty - Hays Kas

Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... Feet

Show depth and thickness of all water, oil and gas formations.  
OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 230 feet to 40 feet for each plug set.

Hole was filled with heavy drilling fluid to a depth of 230ft. First plug was set and hulls + rocks were placed on top of plug with 15 sacks cement. Hole was filled to 40 ft second plug was set and hulls and rocks were placed on top of plug and 10 sacks of cement. Hole was filled to bottom of cellar

RECEIVED  
STATE CORPORATION COMMISSION

JUL 17 1953

7-17-53

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to... Tom Elliott  
Address... 121 N. Mission, Council Grove Kas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.  
Jack Herndon

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] Vice-President of Herndon Drilling Company

SUBSCRIBED AND SWORN to before me this 15th day of July 1953

My commission expires Sept. 19, 1956

[Signature] Notary Public.

21-6858-RS 2-47-6M

PLUGGING  
FILE SEC 33 T 9 R 16W  
BOOK PAGE 112 LINE 29

5-163-00485-00-00

WELL LOG ON CONGER #1

Spudding date: 6/22/53  
Date casing set: 6/22/53  
Date rotary completed: 7/3/53  
Date cable completed:

Location:

Section 33-9S-16W - Rooks County, Kansas

FROM	TO	FORMATION	REMARKS
0	240	Surface Hole	Ran 6 Jts. 8-5/8" 22.7# S.W. Casing @ 240'
240	1750	Shale & Shells	Cemented w/ 175 Sx. Bulk Cement
1750	2990	Shale & Lime	
2990	3460	Lime	
3460	3497	Lime & Shale	
3497	3510	Lime	
3510	3530	Lime & Shale	
3530	3575	Lime	
3575		Total Depth	

Plugged w/ 15 Sx. Cement on bottom plug and 10 Sx. on top plug

RECEIVED  
STATE GEOLOGICAL COMMISSION  
JUL 17 1953  
CONSERVATION DIVISION

7-17-53

**PLUGGING**  
FILE SEC 33 T 9 R 16W  
BOOK PAGE 112 LINE 29

Subscribed and sworn to before me this 15th day of July, 19 53

I certify the above and foregoing to be a true and exact copy of the original driller's log on the CONGER #1

*Jessie M. Nearing*  
Notary Public  
My commission expires: 4/22/57

HERNDON DRILLING COMPANY  
*O J Moore*  
By: Assistant Secretary  
Title: