


15-163-00801-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 33 Twp. 9 Rge. 16W (✓) (X)
Location as "NE/CNW/SW" or footage from lines. SW SW NW
Lease Owner Artnell Company
Lease Name Colohan Well No. 1
Office Address 533 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2/18/60 19
Application for plugging filed 2/18/60 19
Application for plugging approved 2/18/60 19
Plugging commenced 2/18/60 19
Plugging completed 2/18/60 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Rooks Co., Hays, Kansas.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3520 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 224' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled Hole from Total Depth 3520, to 630' with Rotary Mud; 1st plug set at 630' with 20 sx. cement; Filled hole to 225' with Rotary Mud; Set 2nd Plug at 225' with 20 sx. Cement; Filled with Mud to 40'; Set plug at 40' with 10 sx. cement; Filled to Surface with Rotary Mud.

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1960

CONSERVATION DIVISION
Wichita, Kansas

226-60

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor National Drilling Co., Inc.
Address 533 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bonald R. Douglass (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bonald R. Douglass

533 Petroleum Building
(Address) Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 22 day of February, 19 60

My commission expires 2/24/60

Betty Baker
Betty Baker Notary Public.



15-163-00 801-00-00

RECEIVED
FEB 26 1960
COMMISSION DIVISION
Wichita, Kansas

DRILLERS LOG

2-26-60

CASING RECORD:
8 5/8" @ 224'

COMPANY: Artnell Company
533 Petroleum Building
Wichita, Kansas

TOTAL DEPTH:
3520'

CONTRACTOR: Nat'l Drlg. Co.

COMMENCED: 2/11/60

COMPLETED: 2/18/60

DESCRIPTION:
Colohan No. 1
SW SW NW
33-9S-16W
Rooks Co., Kansas

ELEVATION: 2010 KB

| FORMATION | FROM | TO |
|----------------|------|------|
| Post Rock | 0 | 40 |
| Shale | 40 | 225 |
| Shale & Shells | 225 | 850 |
| Sandy Streaks | 850 | 950 |
| Shale & Shells | 950 | 1210 |
| Anhydrite | 1210 | 1250 |
| Shale & Shells | 1250 | 1720 |
| Shale & Lime | 1720 | 1990 |
| Lime & Shale | 1990 | 2115 |
| Lime | 2115 | 2480 |
| Lime & Shale | 2480 | 2640 |
| Shale & Lime | 2640 | 2965 |
| Lime | 2965 | 3520 |
| R.T.D. | 3520 | |

I certify that this is a true and correct copy of the above log to the best of my knowledge.

NATIONAL DRILLING COMPANY, INC.

Howard A. Stoskopf
Howard A. Stoskopf, President

Subscribed and sworn to before me this 23 day of February, 1960.

Betty Baker
Betty Baker-Notary Public

My Commission Expires: 2/24/60