


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-163-20278.00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 34 Twp. 9S Rge. _____ (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner Tilco et al
Lease Name Becker "A" Well No. 1
Office Address P.O. Box 486 Gt. Bend,
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed December 14 19 69
Application for plugging filed December 14 19 69
Application for plugging approved December 14 19 69
Plugging commenced December 14 19 69
Plugging completed December 14 19 69
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3421 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	249'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill w/mud to 540' & 70 sacks 50/50 pozmix & 6% Gel,
Mud to 240' & 20 sacks 50/50 Pozmix 6% Gel, Hull & Plug
140' w/10 sacks 50/50 Pozmix 6% Gel.

1/6/70
RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address P.O. Box 486 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

James R. Rodgers (employee of owner) or (owner or operator) of the above-described

well, hereby duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James R. Rodgers
James R. Rodgers
P.O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of January, 19 70

My commission expires November 13, 1973

Helen L. Lindenmuth
Helen L. Lindenmuth Notary Public.



15-163-20278-00-00

DRILLER'S LOG

COMPANY Tilco et al
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: BECKER "A" #1
 LOCATION: SE SE NE SECTION 34-9S-16W
 ROOKS COUNTY, KANSAS
 COMMENCED: 12-8-69
 COMPLETED: 12-14-69

0	38	Post Rock
38	249	Blue Shale
249	635	Shale
635	900	Sand & Shale
900	1201	Shale Red Bed
1201	1238	Anhydrite
1238	1470	Shale
1470	1860	Shale w/Lime
1860	3006	Lime & Shale
3006	3421	Lime
	<u>3421</u>	<u>RTD</u> D&A

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 6 1970
 CONSERVATION DIVISION
 Wichita, Kansas
 1/6/70

8 5/8" 20# New Surface Casing set @ 249' cemented with 165 sacks
 Common 2% C.C. Cement did circulate.

I, James R. Rodgers, do hereby certify that the above and foregoing is a true and correct copy of the log of the Becker "A" #1 Well, located SE SE NE of Section 34, Township 9 South, Range 16 West, Rooks County, Kansas, as reflected by the records of Leben Drilling, Inc.

James R. Rodgers
 James R. Rodgers

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 2nd day of January, 1970.

Helen L. Lindenmuth
 Helen L. Lindenmuth

My Commission Expires:
 November 13, 1973