

15-163-20294-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 35 Twp. 9 Rge. 16 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C SE NW

Lease Owner John O. Farmer, Inc.

Lease Name Becker Well No. One

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 23, 19 70

Application for plugging filed February 23, 19 70

Application for plugging approved February 23, 19 70

Plugging commenced February 23, 19 70

Plugging completed February 23, 19 70

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3,600 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	233'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole w/ heavy mud
Set bridge plug @ 600'
Pump 70 sax cement on plug thru 4 1/2" drill pipe
Set bridge plug @ 210'
Pump 30 sax cement on plug thru 4 1/2" drill pipe
Set bridge plug @ 40' w/ 1/2 sax hulls on plug
Dump 10 sax cement on plug to cellar

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1970
CONSERVATION DIVISION
Wichita, Kansas

2-27-70

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.

Address Shields Bldg., Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss. R. J. Shields contractor

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. J. Shields

Shields Bldg., Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 26th day of February, 19 70

My commission expires May 26, 1971

Luth Phillips Notary Public.

Shields


13-163-20294-00-00

Russell, Kansas

WELL LOG

Operator: John O. Farmer, Inc.
 Well: Becker #1
 Commenced: February 16, 1970
 Completed: February 23, 1970
 Contractor: Shields Drilling Co., Inc.

Well Description C SE NW
 Sec. 35-9S-16W
 Rooks County, Kansas



CASING RECORD

Size:	Run	Pulled
8 5/8"	233'	Cmtd. w/150 sax

Elevation:
 Treatment:
 Production: D & A
 Tops:

Figures Indicate Bottom of Formations

Shale & sand	240'
Shale & shells	815'
Shale & redbed	1,254'
Anhydrite	1,290'
Shale & shells	1,775'
Shale & lime	2,510'
Lime	3,600'

RTD

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 27 1970
 CONSERVATION DIVISION
 Wichita, Kansas

2-27-70

Notes