


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

GRAHAM County, Sec. 30 Twp. 9s Rge. 21 (X) (W)  
Location as "NE/CNW/SW" or footage from lines. NW SE NW  
Lease Owner PETROLEUM, INC.,  
Lease Name SMITH "AL" Well No. 1  
Office Address R.R. #2, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed SEPTEMBER 23 19 66  
Application for plugging filed SEPTEMBER 23 19 66  
Application for plugging approved SEPTEMBER 23 19 66  
Plugging commenced SEPTEMBER 23 19 66  
Plugging completed SEPTEMBER 23 19 66  
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE

If a producing well is abandoned, date of last production NONE 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3924' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	215'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 540', FOLLOWED BY WOODEN PLUG, PLACED 20 SACKS CEMENT ON TOP OF PLUG. MUD TO 210', FOLLOWED BY WOODEN PLUG, PLACED 1/4 SACK HULLS AND 20 SACKS CEMENT ON TOP OF PLUG. MUD TO 40', FOLLOWED BY WOODEN PLUG, PLACED 1/2 SACKS HULLS AND 10 SACKS CEMENT ON TOP OF PLUG TO BASE OF WELL CELLAR.

RECEIVED  
STATE CORPORATION COMMISSION  
10/13/66  
OCT 13 1966  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor GARVEY DRLG. CO.  
Address R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.

MONTE CHADD (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.  
(Signature)

R.R. #2., GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of OCTOBER, 19 66

My commission expires MAY 28, 1969  
Richard H. Dumbler  
Notary Public.

# WELL LOG

COMPANY **Petroleum, Inc.**

SEC. 30 T. 9S R. 21W

FARM **Smith "AL"** NO. 1


LOC. **NW SE NW**

TOTAL DEPTH **3924'**

COUNTY **Graham**

COMM. **9-15-66** COMP. **9-23-66**

CONTRACTOR **Garvey Drilling Company**



CASING **8 5/8" @ 215' w/175 sx**

ELEVATION **2359' DF**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

- 180' Top Soil, Sand and Shale
- 1000' Shale
- 1225' Shale and Sand
- 1400' Shale
- 1535' Sand
- 1866' Shale and Shells
- 1898' Anhydrite
- 2000' Red Bed
- 2260' Shale and Shells
- 2469' Shale and Lime
- 2915' Lime and Shale
- 3560' Shale and Lime
- 3924' Lime
- 3924' RTD

**RECEIVED**  
STATE CORPORATION COMMISSION  
**OCT 18 1966**  
CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas }  
County of Barton } ss

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Smith "AL" No. 1 well.

*Sam N. Stephens*

Subscribed and sworn to before me this 7th day of October 19 66

My Commission Expires: November 5, 1969

*Richard D. Day*  
NOTARY PUBLIC