


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

GRAHAM COUNTY, KANSAS County. Sec. 32 Twp. 9S Rge. 21W (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW NW NE
Lease Owner K & E DRILLING, INC.
Lease Name 719 Union Center EICHMAN Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed July 14th, 1959 19____
Application for plugging filed July 14th, 1959 19____
Application for plugging approved July 14th, 1959 19____
Plugging commenced July 14th, 1959 19____
Plugging completed July 14th, 1959 19____
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3912' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	211'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 550' set plug with 20 sx cement thru drill pipe. Filled with heavy mud to 210' set plug with 20 sx cement thru drill pipe. Filled with heavy mud to 40' set solid bridge with 10 sx cement to base of cellar. Job complete 7-14-59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
Dale Silcott of K & E DRILLING, INC.
719 Union Center, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of July, 19 59

Patricia M. Edwards, Notary Public.

My commission expires August 11th, 1962.

PLUGGING
FILE SEC. 32 9 R 21W
BOOK PAGE 52 LINE 13

7/18/59
JUL 18 1959

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S WELL LOG

OPERATOR: K & E DRILLING, INC.
719 Union Center
Wichita 2, Kansas

WELL NAME: #2 EICHMAN
LOCATION: SW NW NE
Sec. 32-9S-21W
GRAHAM CO, KANSAS

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: July 6th, 1959

CASING RECORD: 8-5/8" @ 211' (150 sx cmt)

COMPLETED: July 14th, 1959

ELEVATION: 2324' KB

ROTARY TOTAL DEPTH: 3912'

PRODUCTION: D & A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Surface Soil & Clay	50
Sand & Clay	95
Shale	211
Shale & Shells	1040
Shale & Sand	1295
Sand	1520
Red Bed & Shale	1585
Red Bed	1785
Anhydrite	1825
Shale & Shells	2485
Shale & Lime	2550
Lime & Shale	2875
Lime	2980
Lime & Shale	3270
Lime	3815
Lime & Shale	3860
Shale & Lime	3912
R.T.D.	3912

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, Dale Silcott of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Dale Silcott

Dale Silcott

Subscribed and sworn to before me this 17th day of July 1959

Patricia M. Edwards

Patricia M. Edwards, Notary Public.

My Commission expires: August 11th, 1962.

PLUGGING
FILE SEC 32-19 R 21W
BOOK PAGE 52 LINE 13

RE
STATE COR.

JUL 18 1959

COPY SIK

