

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 32 Twp. 9S Rge. 21 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE/4 NE/4 SE/4

Lease Owner Walters Drilling Co., Inc.

Lease Name Early Well No. 1

Office Address 510 Orpheum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 4, 19 53

Application for plugging filed August 8, 19 53

Application for plugging approved August 8, 19 53

Plugging commenced August 25, 19 53

Plugging completed August 25, 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3939 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Water & Oil	3916'	3939'	5 1/2"	3934.60'	3480.50'
	Cemented surface casing with 100 sacks cement and 1 Gal. Chloride					
	Cemented oil string with 50 sacks cement					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

P. B. 3921 to 3886 Cemented, 5 sx
 3886 to 160 Heavy mud
 160 to 150 Rock Bridge
 150 to 105 Cement, 15 sx
 105 to 35 Heavy mud
 35 to 30 Rock Bridge
 30 to bottom of cellar - Cement 10 sx.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pulling Inc. (Permit #21)
Address 629 W. Broadway, Stafford, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Robert F. Walters (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters

510 Orpheum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of September, 19 53

Pauline Reubien
Notary Public.

My commission expires March 10, 1956

PLUGGING
FILE SEC 32 T 9 R 21W
BOOK PAGE 120 LINE 22

RECEIVED
STATE CORPORATION COMMISSION
9/4/53
SEP - 4 1953
CONSERVATION DIVISION
Wichita, Kansas

DAILY NO. 3

Location:	SE 1/4 Sec. 32-48-21W Crawford County, Kansas	Date Drilled: 7-13-53
Operator:	Walters Drilling Co., Inc.	Rotary Completion: 7-26-53
Contractor:	Walters Drilling Co., Inc.	Elevation: 2335 Cr 2328 BP 2340 BS
Surface Casing:	8 5/8" set at 150 Ft. with 100 sacks cement and 1 sack Cal. Chloride	
Oil String:	5 1/2" set at 3926' with 50 sacks cement	

LOG

(Figures indicate bottom of formation)

Surface	0 to 150
Shale and Shells	915
Sand and Shells	989
Shale and Sand	1335
Sand	1535
Shale and Shells	1808
Anhydrite	1850
Shale and Shells	2901
Shale and Lims	3407
Lims	3514
Lims and Shale	3521
Lims	3715
Lims and Shale	3921
Total Depth (Rotary)	3921

Cable tool total depth 3935 HFW

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO., INC.

By Robert F. Walters

Subscribed and sworn to before me
this 28th day of July, 1953.

Pauline Neubricker
Notary Public

My commission expires: March 10, 1956

