

15-065-03424-00-00

API NUMBER NA

LEASE NAME Denning

WELL NUMBER 3

SPOT LOCATION 330FSL

4290FEL
 SEC. 32 TWP. 9S RGE. 21 (E) of (W)

COUNTY Graham

Date Well Completed 2-14-53

Plugging Commenced 4-27-88

Plugging Completed 4-27-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR White Hawk Oil Company

ADDRESS P.O. Box 1150 Great Bend, Kansas 67530

PHONE # (316) 792-4309 OPERATORS LICENSE NO. 5163

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? X If not, is well log attached? _____

Producing formation Lansing-K.C. Depth to top 3565' bottom 3588' T.D. 3651'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	170'	none
				5-1/2"	3,651	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. L-K Wireline perforated Anhydrite @ 1,780' with 2 holes, and Dakota @ 1,000' with 2 holes. Allied Cementing Co. pumped down casing with 200 sks. ATL cement and 4 sks. hulls. Pumped down 8-5/8" with 100 sks. ATL cement and 1 sk. hulls. Shut well in.

State Pluggger on location- Carl Goodrow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc.

Address P.O. Box 31, Russell, Kansas 67665

License No. RECEIVED
 STATE CORPORATION COMMISSION

5/31/88
 MAY 31 1988

STATE OF _____ COUNTY OF _____, ss.

Robert E. Lundberg (employee of operator) or CONSERVATION DIVISION
 (operator) of above-described well, being first duly sworn on oath, says: That or Wichita, Kansas
 I have knowledge of the facts, statements, and matters herein contained and
 the log of the above-described well as filed that the same are true and
 correct, so help me God.

(Signature) Robert E. Lundberg
 (Address) P.O. Box 1150, Great Bend, Ks.

SUBSCRIBED AND SWORN TO before me this 26th day of May, 1988

Mildred Carter
 Notary Public

My Commission expires: 5-11-91

Denning # 3

32-9-21
 Grahan Co SE/SW/SW
 Elev 2302

8 5/8 170' casing

G.L.

2/8/53 5 1/2" 14 3/4 3646.87 117 jts 100 sax
 T.D. KB 3903 Schlum 3849'

Anhydrite 1782
 Heb 3491
 K.C. top 3529
 K.C. B 3756
 Lan 3509
 Simpson 3869
 Top Arb 3885 (-1531)

2/13/53 Drill Plug to 3626'
 Perforate 3566-70 12 holes
 " 3570-74 12 holes
 " 3584-88 12 "
 " 3586-90 12 "
 " 3580-84 12 "
 " 3573-80 12 "

Show of oil

2/14/53 Acidize 500 gals 300# mas. swab 3 bbls hr.

2/16/53 run 117 jts to 2" EUE tubing
 1 jt. anchor 3' perf - 8' barrel
 8'-3'-pup on top
 143 3/4x25 type 81 rods
 8 cups WHI cup value 1 3/4" snubber cages

3/2/53
 acidize 1000 gals Jel x 100
 max 450# on tubing
 " 650# on csg.

3/10/53 state test 38x20 stroke
 24 hr 147 bbls

RECEIVED
 STATE CORPORATION COMMISSION

MAR 11 1953

CONSERVATION DIVISION
 Wichita, Kansas