

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 32 TWP. 9 RGE. 21 E/W
Location as in quarters or footage from lines:
NE SE SW

Locate Well
correctly on above
Section Platt.

Lease Owner White Hawk Oil Company
Lease Name Denning Well No. 2
Office Address P.O. Box 1150, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed 6-7-50
Application for plugging filed 6-14-85
Plugging commenced 7-9-85
Plugging completed 7-10-85
Reason for abandonment of well or producing formation Oil reserves depleted

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
Producing formation Kansas City Depth to top 3530 bottom 3537 T.D. 3857
Show depth and thickness of all water, oil and gas formations. C.I.B.P.-3490

OIL, GAS OR WATER RECORDS P.B.T.D.-3490 Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

7-9-85 Tried to pump down 9 5/8" pipe but could not at 400#. Pipe was cemented off from Previous squeeze job.

Run 2" tubing and tagged bridge plug at 3490'. Pulled tubing to 3480'. Pumped 50 sks cement. Pulled tubing to 2878'. Pumped 13 sks. gel. Pulled tubing to 1566' Pumped 140 sks cement. Cement circulated to surface. Pulled all of tubing out. Pumped 10 sks. cement for displacement.

7-10-85 Cut pipe off in cellar; found cement down 36'. Filled to Surface with cement.

Cement used: 200 sks 60-40 poz. 6% gel, 3% C.C.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Halliburton Services.

STATE OF Kansas COUNTY OF Barton, ss.
Robert E. Lundberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert E. Lundberg
P.O. Box 1150, Great Bend, Ks
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 85

My Commission expires:



J. Pete Steinbacher
Notary Public.
STATE CORPORATION COMMISSION

8/7/85
AUG 7 1985