

15-065-01499-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Graham County. Sec. 26 Twp. 9 Rge. 21W (E) (W)
Location as "NE/CNW/SW" or footage from lines S/2 NW NW
Lease Owner Bennett & Roberts Oil Operations
Lease Name Cox "A" Well No. 4
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 2/19 19 49
Application for plugging filed 12/6 19 55
Application for plugging approved 12/7 19 55
Plugging commenced 12/7 19 55
Plugging completed 12/9 19 55
Reason for abandonment of well or producing formation
No longer produced enough oil to operate economically
If a producing well is abandoned, date of last production 10/10 19 55
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3874 Bottom Total Depth of Well 3877 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	187'	None
				5 1/2"	3875'	965'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock from 3877' to 3860'. Dumped 4 sax cement with dump bailer at 3860', top of cement 3835'. Filled hole with mud to 185', set rock bridge, dumped 15 sax cement, top of cement 140'. Filled hole with mud to 35', set rock bridge, dumped 10 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Miller Casing Pulling Co.
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December, 1955

My commission expires 6/17/58 Notary Public.

PLUGGING
FILE SEC 26 T 9 R 21W
BOOK PAGE 22 LINE 14

12/19/55

Cox A#4
Bennett & Roberts Oil Operations

Sec. 26 Twp. 9 Rge. 21
County: Graham, Kansas

Rotary Total Depth: 3877

Top Lansing K.C. - 3551
Top Arbuckle - 3874

Commenced 1/30/49
Completed 2/14/49

S. Oil - 3877

Casing
8 5/8" Set @ 187'
5 1/2" Set @ 3875'

Cement
130 Sacks
75 Sacks

Formation	Depth
Surface Clay	15
Sand & Shale	60
Shale & Shells	610
Shale	930
Shale & Shells	990
Shale	1082
Shale & Shells	1310
Shale & Sand	1475
Shale, Shells, Red Bed	1630
Shale & Red Bed	1785
Anhydrite	1825
Shale & Shells	2330
Lime & Shale	3452
Lime	3798
Lime & Shale	3877

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS OIL OPERATIONS

By *Erin Lake*

Subscribed and sworn to before me this 6th day of December, 1955.

Clara Humana
Notary Public

My Commission Expires 6/17/58

PLUGGING
FILE NO. 3679 R 21w
BOOK PAGE 22 LINE 14