


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham County. Sec. 33 Twp. 9 Rge. 21 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW NW NE  
Lease Owner Herman George Kaiser Producers & Francis Oil  
Lease Name Bragg Well No. 1  
Office Address 909 Palace Bldg. Tulsa, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced March 19 1959  
Plugging completed April 1 1959  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius  
Producing formation Arbuckle Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3856 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>8 5/8"</u>	<u>192'</u>	<u>None</u>
				<u>5 1/2"</u>	<u>3851</u>	<u>815'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand to 3840'. Dumped 5 sx. cement.  
Pulled 5 1/2" Casing.  
Mudded hole to 190', mixed and dumped 10 sx. cement.  
Bailed hole dry, mixed and dumped 15 sx. cement to  
136'. Filled hole with mud to 35', set top of 5' rock  
bridge at 30'. Mixed and put in 10 sx. cement, filled  
to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
4/22/59  
APR 22 1959

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Ace Pipe Pulling Company  
Address Box 304 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
I, W. J. Hall

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Hall

SUBSCRIBED AND SWORN TO before me this 9 day of April, 19 59


(Address) Delmer L. Foster

My commission expires \_\_\_\_\_

Notary Public.

PLUGGING  
FILE SEC. 33 T. 9 R. 21W  
BOOK PAGE 20 LI 7

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Francis Oil & Gas, Inc. Herman George Kaiser Farm Bragg No. 1 Depth 3856  
 Contractor Veeder Supply & Dev'l. Co. Pipe 192" 8 5/8" csg. cemented w/150 sacks cement  
3851 5" csg. cemented w/125 sacks cement  
 Location S1/4 NW NE Sec. 11 Twp. 9 Range 2  
 Commenced 8-3-1954 Completed 8-11-1954 County Grant State Kansas

Sand, gravel, shale	0	138	138
Gravel, gray shale	138	175	37
Shale, gray	175	250	75
Shale, white	250	310	60
Blue shale	310	540	230
Shale, shells	540	910	370
Sand	910	970	60
Shale, shells	970	1270	300
Sand, shale	1270	1500	230
Shale, shells, redbed	1500	1760	260
Anhydrite	1760	1805	45
Shale, shells	1805	2100	295
Shale	2100	2360	260
Lime, shale	2360	3525	1165
Lime	3525	3845	320
Conglomerate	3845	3851	6
Arb. Lime	3851	3856	5
Total Depth			

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 9 1955  
 CONSERVATION DIVISION  
 WASHINGTON, D.C.

AFFIDAVIT

STATE OF KANSAS }  
 Montgomery County } SS

Floyd W. Hill, of lawful age, being first duly sworn upon oath, deposes and says:

That I am a resident of Cherryvale, Montgomery County, Kansas, that I know and on oath hereby state that the above drilling log covering the Bragg #1 well located in Section 33-9-21, Grant County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

BY Floyd W. Hill  
 Floyd W. Hill

Subscribed and sworn to before me this 16th day of August, 1954.

Edna Samson  
 Notary Public

My commission expires July 11, 1956.

PLUGGING  
 FILE SEC. 33 T. 9 R. 21 LW  
 BOOK PAGE 20 LINE 7