


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-065-01504-00-00

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec. 33 Twp. 9 Rge. 21 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW NW NE
Lease Owner Herman George Kaiser
Lease Name Bragg Well No. 2
Office Address 905 Palace Bldg. Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced Mar. 1 1960
Plugging completed Mar. 12, 1960
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A.D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3863' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	195'	none
				5 1/2	3858'	2731'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 3863' to 3855'. Mixed and dumped 3 sx. cement from 3855' to 3831'. Pulled 5 1/2. Mudded from 3831' to 195'. Set 5' rock bridge from 195' to 190'. Mixed and dumped 25 sx. cement from 190' to 115'. Mudded from 115' to 30'. Set 5' rock bridge from 35' to 30'. Mixed and dumped 10 sx. cement from 30' to base cellar.

RECEIVED
STATE CORPORATION COMMISSION
3/23/60
MAR 25 1960
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.
Address Box 304 Great Bend, Ks.

STATE OF Kansas, COUNTY OF Barton, ss.
I, W.J. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W.J. Hall
(Address) _____

SUBSCRIBED AND SWORN to before me this 17 day of March, 19 60

My commission expires _____
Delmer L. Foster
Notary Public.



Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Francis Oil and Gas, Inc. Farm Bragg No. 2 Depth 3859'
 Contractor Veeder Supply & Development Co. Pipe 3859' 8 5/8" csg. cemented w/125 sacks cement.
 Location NE/4 Sec. 33 Twp. 9 Range 21
 Commenced 9-10-1954 Completed 9-20-1954 County Graham State Kansas

Cellar	0	9	9	TOPS	
Shale, sand	9	106	97		
Gray shale	106	270	164	Heeber	3488
White shale	270	910	640	Toronto	3506
Sand	910	960	50	K. C.	3528
Shale, shells	960	1250	290	Conglomerate	3823
Shale, shells, red bed	1250	1784	534	Arbuckle	3856
Anhydrite	1784	1820	36		
Shale, shells	1820	2100	280		
Lime, shale	2100	2505	405		
Lime, shale pyrite	2505	2630	125		
Lime, shale	2630	3550	920		
Lime	3550	3859	309		
Total Depth	3859				

AFFIDAVIT

STATE OF KANSAS)
 Montgomery County) SS

Floyd W. Hild, of lawful age, being first duly sworn on oath, deposes and says:

THAT he is a resident of Cherryvale, Montgomery County, Kansas; that he knows and on oath hereby states that the above drilling log covering the Bragg #2 well located in Section 33-9-21, Graham County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By: Floyd W. Hild
 Floyd W. Hild

Subscribed and sworn to before me this 22nd day of September, 1954.

Leo C. Veeder
 Notary Public

My commission expires: November 1, 1956.