


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 33 Twp. 9 Rge. 21 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines. SE NE NW
Lease Owner American Petrofina Company of Texas
Lease Name Cox Well No. 2
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 5-17-63 _____ 19____
Plugging completed 5-20-63 _____ 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3886 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	198'	None
				5-1/2"	3875'	914'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole to 3865' and dumped 5 sacks of cement @ 3865' with dump bailer. Pulled 5 1/2" casing to 600' and circulated with 21 sacks of gel mud and 20 sacks of cement. Pulled 5 1/2" casing to 200' and pumped 20 sacks of cement. Pulled balance of 5 1/2" casing, bailed hole to 35' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
6/3/63
JUN 3 1963

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~OWNER OR OPERATOR~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of May, 19 63

My commission expires May 20, 1964 Milton J. Volin Notary Public.



R
DRILLER'S LOG

El Dorado Refining Co.
306 Koch Building
Wichita, Kansas

Elevation: 2321' KB
2318' DF
8-5/8" x 5-1/2" Head 4.20'
below DF or 7.20 below KB.

Cox #2

SE NE NW
Sec. 33-9S-21W
Graham County, Kansas

Casing Record:
8-5/8" @ 198' w/135 sks.
bulk cement and 100# cc. K. B.

Well Comm: 5-29-54
Well Comp: 6-11-54

5-1/2" @ 3875' w/75 sks. bulk
cement. D. F.

Contractor: E. K. Carey Contractor, Rig #1, Box 620, McPherson County, Kansas.
Geologist: Dale Goodrich, Wichita, Kansas.

Figures indicate bottom of formation K. B.

Cellar & base	7
Shale	70
Sand	120
Shale and shells	900
Sand	1000
Sand, Shale and Shells	1100
Shale	1300
Sand	1530
Shale and red bed	1760
Red Rock and Shale	1800
Anhydrite	1830
Shale	1930
Shale and shells	2130
Shale and lime	2615
Lime	2662
Lime and Shale	2700
Shale and Lime	2805
Lime and shale	3535
Lime	3772
Cong.	3820
Lime and shale	3830
Conglomerate	3877
Arbuckle lime	3880 TD
	3886 CTTD

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1963

CONSERVATION DIVISION
Wichita, Kansas

Geologist Tops:
Derrick Floor 3' below K. B.

Heebner	3504 (-1186)
Toronto	3528 (-1210)
Kansas City	3543 (-1228)
Cong.	3830 (-1512)
Arbuckle	3874 (-1556)
Total Depth	3877
Set 5-1/2" @ 3875' or 2' off bottom.	

DST-3554 to 3597 KB, using 43'
anchor, tool open 30 M very weak
blow, closed 20 M. BHP 1380#.

DST-3610 to 3645 KB., using 35'
anchor, tool open 30 M. Recovered
8' drlg. mud. Closed 10 M. for BHP
of 350#.

This is to certify that the above information is to the best of my knowledge true and correct.

SUBSCRIBED AND SWORN TO before me this 12th day of June, 1954.

E. K. CAREY CONTRACTOR

S/ Herbert Rhoton
BY Herbert Rhoton, Superintendent

s/ Notary Public

My commission expires: November 13, 1956