


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Graham County, Sec. 33 Twp. 9 Rge. 21 (E) W (W)

Location as "NE/CNW/SW" or footage from lines ~~XXXXXXXXXX~~ NW NW NW  
Lease Owner American Petrofina Company of Texas  
Lease Name Cox Well No. 5  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 5-22-63 19  
Plugging completed 5-23-63 19  
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3903' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	255'	None
				5-1/2"	3900'	614'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, sanded hole to 3895' and dumped 5 sacks of cement. Pulled 5 1/2" casing to 600' and circulated pipe with 18 sacks of salt gel and 20 sacks of cement. Pulled balance of 5 1/2" casing, bailed hole to 200', set rock bridge and ran 20 sacks of cement. Mudded hole to 35' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
6/3/63  
JUN 3 1963

PLUGGING COMPLETE.

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of May, 1963

My commission expires May 20, 1964 Notary Public.



EL DORADO REFINING COMPANY  
 Cox #5

C 24 24 24 Sec. 33-28-21W  
 Graham County, Kansas

Comm: May 12, 1946  
 Comp: May 19, 1946  
 Total Depth: 3903'

RECEIVED  
 STATE CORPORATION

MAY 14 1963

CONSERVATION  
 Wichita, Kansas

Casing

8 5/8" set @ 255'

5 1/2" set @ 8900'

DV Tool " " 1600'

Temp. Survey, Top cement @ 650'

FORMATION

Clay & shale  
 Sand  
 Shale  
 Shale  
 Shale & sand  
 Shale & sand  
 Red shale- shalls  
 Anhydrite  
 Anhydrite  
 Shale & shalls  
 Shale & lime  
 Lime  
 Lime & shale

DEPTH

150 casing  
 575 casing

0 - 60  
 60 - 95  
 95 - 255  
 255 - 580  
 580 - 1240  
 1240 - 1555  
 1555 - 1795  
 1795 - 1820  
 1820 - 1840  
 1840 - 2050  
 2050 - 2545  
 2545 - 3520  
 3520 - 3903

STATE OF KANSAS }  
 GRAHAM COUNTY } ss

I hereby certify that the above information is true and correct to the best of my knowledge.

*Bob Silcott*

Subscribed and sworn to before me this 21st day of May, 1946.

*James Maden*  
 Notary Public

My commission expires: June 25, 1946.

TOPS (Elev. 2335 D.F.)

	Datum
Heebner	-1180
Toronto	-1207
Lans.	-1217
B/Kans C.	-1446
Congl.	-1511
Arbuckle	-1558
RTD	-1565